

 OneSubsea A Cameron & Schlumberger Company	 TOTAL E&P ANGOLA	
GirRI MPP - HANDBOOK		
Document number: AO-050-GMP-310-000324		
Revision: 02 Status: AFC		
Document Type: MAN	System / Subsystem: 04	Discipline: PJM
Contractor ref: DOC-0067899_revC		Rev. Date: 20-Apr-2015
Phase : DE		Page 1 of 160 Class : 2

GirRI MPP - HANDBOOK

Rev.	Status	Date	Revision memo	Issued by	Checked by	Approved by
02	AFC	20/APR/2015	Approved for construction	SAA	HHA	IFA
01	AFC	03/MAR/2015	Approved for construction	MFL	HHA	IFA
00	IFR	09/JAN/2015	Released	MFL	HHA	IFA

This document is the property of GOMMA. It must not be copied, reproduced or disclosed to others without written authorisation from the Company.


Engineering Change Order: NA

Handbook GirRI MPP Station



TOTAL

TOTAL E&P ANGOLA



TOTAL



Table of Contents

1	System information	7
1.1	Project data	7
1.2	Well data	7
1.3	General information	8
1.4	Abbreviations and nomenclature	9
1.5	Equipment list	10
1.6	Subsea MPP system	23
1.7	Scope of supply	24
1.8	MPP Station assembly	30
1.9	Overview GirRI	31
1.10	Reference list	31
2	Foundation	32
2.1	Foundation reference list	32
2.1	Foundation features	33
2.1	Foundation Interface drawing	34
3	SLS	38
3.1	SLS reference list	38
3.1	SLS features	39
3.2	SLS interface drawing	40
4	MPP Module	44
4.1	MPP Module reference list	44
4.2	MPP Module scope of supply	45
4.2.1	MPP Module P70 w/retrievable items	45
4.2.2	MPP Module P80 w/retrievable items	46
4.3	MPP Module interface drawing	47
5	Process flow	54
5.1	Valve data	56
5.1.1	V2-1, V2-2	56
5.1.2	V51-1, V51-2, V52-1, V52-2	56
5.1.3	V3-1A, V3-1B, V3-2A, V3-2B	56
5.1.4	V5-1, V5-2	57

5.1.5	V70-1, V70-2	57
5.1.6	V71-1, V71-2, V72-1, V72-2	57
5.1.7	V82-1, V82-2	57
5.1.8	V80, V83-1, V83-2	58
5.1.9	V20-1, V20-2, V30-1, V30-2	58
5.1.10	V4-1, V4-2	58
5.1.11	CF1, CF2	58
5.2	MPP System – P&ID – MPP Station P70	59
5.3	MPP System – P&ID – MPP Station P80	62
6	Pump Unit.....	65
6.1	Pump Unit reference list	65
6.2	Pump Unit interface drawing	66
7	MPP	72
7.1	MPP reference list	72
7.2	MPP overview.....	73
7.3	MPP details.....	74
7.4	MPP cross section.....	75
7.5	MPP GA drawing.....	76
7.6	MPP technical description.....	78
7.7	MPP working area	79
7.8	MPP motor	80
7.9	MPP general requirements	81
7.10	MPP design conditions	81
8	MPFM	82
8.1	MPFM reference list	82
8.1	MPFM GA drawing	83
9	SCM.....	85
9.1	SCM reference list	86
9.2	SCM scope of supply.....	87
9.3	SCM interface drawing	89
10	MFCV (V4-1 / V4-2).....	91
10.1	MFCV reference list	92
10.2	MFCV placement	93
10.1	MFCV technical description.....	94

10.2	MFCV GA drawing.....	95
11	DPU.....	100
11.1	DPU reference list.....	100
11.2	DPU scope of supply.....	100
11.3	DPU GA/interface drawing.....	101
12	CCV (V81-1 / V81-2).....	107
12.1	CCV reference list.....	107
12.2	CCV placement.....	108
12.3	CCV GA drawing.....	109
13	Tie in.....	111
13.1	Tie in reference list.....	111
13.2	Tie in interface drawing.....	112
14	Jumpers and wiring.....	114
14.1	Signal jumper layout drawing.....	114
14.2	SCM-SPCU FO connection diagram.....	117
14.3	FO Flying Lead assembly drawing.....	119
14.4	SCM-SPCU LV connection diagram.....	121
14.5	LV Flying Lead assembly drawing.....	123
14.6	Electrical jumper diagram.....	125
15	ROV intervention/ tooling.....	129
15.1	ROV intervention / tooling reference list.....	129
15.2	PU running tool.....	129
15.3	PU installation tool.....	129
15.4	Simplified PU installation tool.....	130
15.1	SCM installation tool.....	131
15.2	MFCV – Running tool.....	131
15.3	Flying Leads Deployment Frame.....	132
15.4	Tooling required.....	133
15.5	PU running tool interface drawing.....	135
15.1	PU installation tool interface drawing.....	139
16	Control system.....	142
16.1	Control system reference lists.....	142
16.2	Block diagram P70.....	143
16.3	Block diagram P80.....	144

16.4	Control fluid schematic	145
16.5	Control fluid data.....	146
16.6	Chemical fluid schematic P70.....	147
16.7	Chemical fluid schematic P80.....	148
17	Barrier system	149
17.1	Barrier fluid schematics	149
17.2	Barrier fluid data	149
18	PCM	150
18.1	PCM reference list	150
18.2	PCM internal.....	151
18.3	PCM internal assembly drawing.....	152
18.4	PCM external	154
18.5	PCM external assembly drawing	155
18.1	PCM equipment.....	158
18.2	PCM transport and installation	160

1 System information

1.1 Project data

Description	Data
Design temperature	-18 to +90 °C
Design water depth	1450 m
Actual water depth	P70 1360 m / P80 1400 m
Design life	20 years

1.2 Well data

Description	Rosa
Initial reservoir temperature	69 °C
Initial reservoir pressure	269.6 bara at -2600m TVD/MSL
Maximum WHISP	215 bara

1.3 General information

Description	Data
MPP CON Project Number	9060
MPP CON Scope of Supply	AO-050-PJG-310-000237 (MPP CON doc no: ITM-0009639)
Main Interface Drawing	AO-050-GMP-310-000380 (MPP CON doc no: ITM-0058434)
Hydraulic Schematic	AO-050-GSG-310-000102 and AO-050-GSG-310-000103 (MPP CON doc no: DRW-0001208 and DRW-0001209)
MPP CON Project Manager	Inge Fagnastøl
Client	Total E&P Angola
Client specification	According to contract: 1C200 - Out of Country 1C201 - In Country
End User	Total E&P Angola
Country	Angola
Project	GirRI

1.4 Abbreviations and nomenclature

API	American Petroleum Institute standards
BF	Barrier Fluid
BR	Barrier Return
BS	Barrier Supply
CCR	Central Control Room
CCV	Chemical Control Valve
CF	Control Fluid
CI	Company Items
CIV	Chemical Injection Valve
COMPANY	Total E&P Angola
CR	Conductor Resistance
CTV	Chemical Throttle Valve
CV	Choke Valve
Cv	Coefficient of flow
DCV	Directional Control Valve
DMPP	Dummy MPP
DNV	Det Norske Veritas
E&P	Exploration and Production
FO	Fibre Optical
FLDF	Flying Lead Deployment Frame
FLOT	Flying Lead Orientation Tool
FPSO	Floating, Production Storage and Offloading
GA	General Arrangement (drawing)
GVF	Gas Volume Fraction
HFL	Hydraulic Flying Lead
HPU	Hydraulic Power Unit
HV	High Voltage
HVAC	Heating, Ventilation and Air Conditioning
ISO	International Organization for Standardization

IT	Installation tool
LV	Low Voltage
MCC	Motor Control Centre
MCT	Multi Cable Transit
MeOH	Methanol
MFCV	Minimum Flow Control Valve
MPFM	Multiphase Flow Meter
MPP	Multiphase Pump
MPP RT	MPP Running Tool
MSL	Mean Sea Level
MWP	Maximum Working Pressure
NA	Not Applicable
OWS	Operator Work Station
P&ID	Piping and Instrument Diagram
PCM	Power & Control Module
PPM	Parts per million
PT	Pressure Transmitter
ROV	Remotely Operated Vehicle
SCM	Subsea Control Module
SDU	Subsea Distribution Unit
SEM	Subsea Electronic Module
SLS	Support and Levelling Structure
SPCU	Subsea Power and Control Unit
TS	Transport Skid
TT	Temperature Transmitter
TVD	True Vertical Depth
UPS	Uninterruptible Power Supply
URT	Universal Running Tool
VSD	Variable Speed Drive
WHISP	Wellhead Shut in Pressure
WI	Water Injection

1.5 Equipment list

Level	BOM Line
1	ITM-0020168/I;1-9060 GirRI SCOPE OF SUPPLY (View)
2	ITM-0020169/A;4-Power and Control Module (View) x 1
3	ITM-0090477/B;3-PCM Steel Structure Assembly (View) x 1
4	ITM-0020170/C;4-Power and Control Module Steel Structure (View) x 1
4	ITM-0090464/B;2-PCM Bumper part 1 x 1
4	ITM-0090465/B;2-PCM Bumper part 2 x 1
4	ITM-0090466/B;2-PCM Bumper part 3 x 1
4	ITM-0090467/B;2-PCM Bumper part 4 x 1
4	ITM-0090478/B;2-PCM Lifting Tools (View) x 1
4	ITM-0090457/B;2-PCM Lifting Tool Shackle A (View) x 8
4	ITM-0090458/B;2-PCM Lifting Tool Shackle B x 2
4	ITM-0090462/B;2-ITM-0090462/B;2-PCM Lifting Tool Spreader BarV x 1
4	ITM-0020196/B;2-9060 GirRI PCM Electrical Installation (View) x 1
3	ITM-0020172/C;3-BF-HPU Assembly P70 (View) x 1
4	ITM-0020173/B;3-Barrier Fluid HPU P70 (View) x 1
4	ITM-0038126/C;2-BF HPU Tubing Assembly (View) x 1
4	ITM-0027621/A;2-CONNECTOR MALE SWAGELOK 1610-1-16 x 3
4	ITM-0085146/A;2-Alco Valves - 3/4" Ball Valve - PB6LM x 1
4	ITM-0085147/A;2-Alco Valves - 1" Ball Valve - PB8LM x 1
4	ITM-0085154/A;1-Fluid Control - 3/4" Clamps - 5555-319 x 10
4	ITM-0085155/A;1-Fluid Control - 1" Clamps - 5555-325 x 10
4	ITM-0085151/A;2-Fluid Control - Stacking Bolt - AFN-3 x 20
4	ITM-0020173/B;3-Barrier Fluid HPU P70 (View) x 1
4	ITM-0065532/B;3-BF HPU OIL PURIFIER x 1
3	ITM-0038127/C;3-BF-HPU Assembly P80 (View) x 1
4	ITM-0038129/B;2-Barrier Fluid HPU P80 x 1
4	ITM-0038126/C;2-BF HPU Tubing Assembly (View) x 1
4	ITM-0027621/A;2-CONNECTOR MALE SWAGELOK 1610-1-16 x 3
4	ITM-0085146/A;2-Alco Valves - 3/4" Ball Valve - PB6LM x 1
4	ITM-0085147/A;2-Alco Valves - 1" Ball Valve - PB8LM x 1
4	ITM-0085154/A;1-Fluid Control - 3/4" Clamps - 5555-319 x 10
4	ITM-0085155/A;1-Fluid Control - 1" Clamps - 5555-325 x 10
4	ITM-0085151/A;2-Fluid Control - Stacking Bolt - AFN-3 x 20
4	ITM-0020173/B;3-Barrier Fluid HPU P70 (View) x 1
4	ITM-0089604/C;3-Nitrogen Booster Pump (View) x 1
3	ITM-0043938/D;2-CF-HPU Assembly P70 (View) x 1
4	ITM-0020174/B;2-Control Fluid HPU P70 x 1
4	ITM-0085160/B;1-CF HPU Tubing Assembly (View) x 1
4	ITM-0027621/A;2-CONNECTOR MALE SWAGELOK 1610-1-16 x 2
4	ITM-0085146/A;2-Alco Valves - 3/4" Ball Valve - PB6LM x 1
4	ITM-0085147/A;2-Alco Valves - 1" Ball Valve - PB8LM x 1
4	ITM-0085154/A;1-Fluid Control - 3/4" Clamps - 5555-319 x 10

Level	BOM Line
4	ITM-0085155/A;1-Fluid Control - 1" Clamps - 5555-325 x 10
4	ITM-0085151/A;2-Fluid Control - Stacking Bolt - AFN-3 x 20
4	ITM-0090373/A;3-CF HPU Shims package x 1
3	ITM-0043940/D;3-CF-HPU Assembly P80 (View) x 1
4	ITM-0038128/B;2-Control Fluid HPU P80 x 1
4	ITM-0085160/B;1-CF HPU Tubing Assembly (View) x 1
4	ITM-0027621/A;2-CONNECTOR MALE SWAGELOK 1610-1-16 x 2
4	ITM-0084307/A;1-Swagelok - 1" Male Tube Adaptor - SS-1610-TA-1-16 x 2
4	ITM-0085146/A;2-Alco Valves - 3/4" Ball Valve - PB6LM x 1
4	ITM-0085147/A;2-Alco Valves - 1" Ball Valve - PB8LM x 1
4	ITM-0085154/A;1-Fluid Control - 3/4" Clamps - 5555-319 x 10
4	ITM-0085155/A;1-Fluid Control - 1" Clamps - 5555-325 x 10
4	ITM-0085151/A;2-Fluid Control - Stacking Bolt - AFN-3 x 20
4	ITM-0090373/A;3-CF HPU Shims package x 1
3	ITM-0020189/C;3-Power Drive System Assembly P70 (View) x 1
4	ITM-0020191/C;3-Input Transformer P70R x 1
4	ITM-0043594/C;3-Input Transformer P70L x 1
4	ITM-0043612/C;2-VSD P70R x 1
4	ITM-0043613/C;2-VSD P70L x 1
4	ITM-0089813/B;3-PCM P70 VSD Maintenance Platform x 1
4	ITM-0089822/B;2-VSD P70 Maintenance Tools x 1
3	ITM-0043595/C;3-Power Drive System Assembly P80 (View) x 1
4	ITM-0089815/A;4-PCM P80 VSD Maintenance Platform x 1
4	ITM-0089823/B;2-VSD P80 Maintenance Tools x 1
4	ITM-0020193/C;5-Output Transformer P80L - Located P70 x 1
4	ITM-0020194/C;2-Output Transformer P80R x 1
4	ITM-0043597/C;3-Input Transformer P80R x 1
4	ITM-0043598/C;3-Input Transformer P80L x 1
4	ITM-0043615/C;2-VSD P80R x 1
4	ITM-0043616/C;2-VSD P80L x 1
3	ITM-0020183/C;2-LV Distribution Board Assembly P70 (View) x 1
4	ITM-0020184/B;3-P70 LV Distribution Board x 1
3	ITM-0056767/C;3-LV Distribution Board Assembly P80 (View) x 1
4	ITM-0056776/B;2-P80 LV Distribution Board Cabinet (View) x 1
3	ITM-0020179/C;4-MCC Assembly P70 (View) x 1
4	ITM-0020180/B;2-P70 MCC x 1
3	ITM-0056768/C;4-MCC Assembly P80 (View) x 1
4	ITM-0056775/B;3-P80 MCC Cabinet x 1
3	ITM-0020181/D;4-SPCU Assembly P70 (View) x 1
4	ITM-0020182/C;2-P70 SPCU Cabinet (View) x 1
4	ITM-0065849/A;6-Topside Fiber Optical Modem - Focal 922 Assembly (View) x 2
4	ITM-0091645/A;2-Hard Disk x 3
4	ITM-0032875/C;3-Server SuperMicro CSE-825 Short (View) x 2
4	ITM-0083848/A;1-Supermicro Front Bezel Cover x 2

Level	BOM Line
4	ITM-0082750/A;1-Win Server 2012 Standard x 3
4	ITM-0083852/A;1-Microsoft Windows 8 Pro x 5
4	ITM-0083853/A;1-WinPro SNGL Upgrade to virtuell x 5
4	ITM-0082749/A;1-Office Pro Plus 2013 SNGL OLP NL x 3
4	ITM-0052474/A;2-Symantec Endpoint Protection x 8
4	ITM-0006534/B;3-Acronis SW x 1
4	ITM-0009265/B;4-Microsoft Server 2008 std Edition OLP x 1
3	<i>ITM-0056769/D;3-SPCU Assembly P80 (View) x 1</i>
4	ITM-0056778/C;2-P80 SPCU Cabinet (View) x 1
4	ITM-0065849/A;6-Topside Fiber Optical Modem - Focal 922 Assembly (View) x 2
4	ITM-0032875/C;3-Server SuperMicro CSE-825 Short (View) x 2
4	ITM-0083848/A;1-Supermicro Front Bezel Cover x 2
4	ITM-0082750/A;1-Win Server 2012 Standard x 1
4	ITM-0083852/A;1-Microsoft Windows 8 Pro x 3
4	ITM-0083853/A;1-WinPro SNGL Upgrade to virtuell x 3
4	ITM-0082749/A;1-Office Pro Plus 2013 SNGL OLP NL x 4
4	ITM-0052474/A;2-Symantec Endpoint Protection x 8
4	ITM-0009265/B;4-Microsoft Server 2008 std Edition OLP x 1
4	ITM-0091645/A;2-Hard Disk x 3
3	<i>ITM-0020185/D;3-UCP Assembly P70 (View) x 1</i>
4	ITM-0020186/C;2-P70 UCP Cabinet (View) x 1
4	ITM-0052474/A;2-Symantec Endpoint Protection x 1
3	<i>ITM-0056773/D;2-UCP Assembly P80 (View) x 1</i>
4	ITM-0056774/C;2-P80 UCP Cabinet (View) x 1
4	ITM-0052474/A;2-Symantec Endpoint Protection x 1
3	<i>ITM-0021571/B;1-Inergen System Assembly P70 (View) x 1</i>
4	ITM-0021574/C;1-P70 Inergen System x 1
3	<i>ITM-0038072/B;1-Inergen System Assembly P80 (View) x 1</i>
4	ITM-0038073/C;1-Inergen system P80 x 1
3	<i>ITM-0021573/A;4-F&G Equipment Assembly P70 (View) x 1</i>
4	ITM-0056783/C;2-P70 F&G System (View) x 1
4	ITM-0080938/B;2-ORBIS IS SMOKE DETECTOR x 8
4	ITM-0080939/B;2-XTRALIS VESDA EARLY WARNING SMOKE DETECTOR x 1
4	ITM-0080940/B;2-ORBIS IS HEAT DETECTOR x 3
4	ITM-0080941/B;2-IR GAS DETECTOR x 9
4	ITM-0080942/B;2-OIL MIST MONITOR x 1
4	ITM-0080943/B;2-OIL MIST DETECTOR x 2
4	ITM-0080944/B;2-COMBINED BEACON AND SOUNDER x 10
4	ITM-0080945/B;2-INERGEN RELEASE PUSHBUTTON x 3
4	ITM-0080946/B;2-FOAM RELEASE PUSHBUTTON x 1
4	ITM-0080947/B;2-INERGEN SYSTEM STATUS PANEL x 2
4	ITM-0096295/A;3-Cooper MEDC HD1 Heat Detector x 6
3	<i>ITM-0056779/A;3-F&G Equipment Assembly P80 (View) x 1</i>
4	ITM-0056782/C;2-P80 F&G System (View) x 1

Level	BOM Line
4	ITM-0080938/B;2-ORBIS IS SMOKE DETECTOR x 8
4	ITM-0080939/B;2-XTRALIS VESDA EARLY WARNING SMOKE DETECTOR x 1
4	ITM-0080940/B;2-ORBIS IS HEAT DETECTOR x 3
4	ITM-0080941/B;2-IR GAS DETECTOR x 9
4	ITM-0080942/B;2-OIL MIST MONITOR x 1
4	ITM-0080943/B;2-OIL MIST DETECTOR x 2
4	ITM-0080944/B;2-COMBINED BEACON AND SOUNDER x 10
4	ITM-0080945/B;2-INERGEN RELEASE PUSHBUTTON x 3
4	ITM-0080946/B;2-FOAM RELEASE PUSHBUTTON x 1
4	ITM-0080947/B;2-INERGEN SYSTEM STATUS PANEL x 2
4	ITM-0096295/A;3-Cooper MEDC HD1 Heat Detector x 6
3	<i>ITM-0021572/A;3-Foam System Assembly P70 (View) x 1</i>
4	ITM-0021575/B;2-P70 Foam System x 1
3	<i>ITM-0056780/A;2-Foam System Assembly P80 (View) x 1</i>
4	ITM-0056781/B;2-P80 Foam System x 1
3	<i>ITM-0056647/A;3-HVAC System (View) x 1</i>
4	ITM-0038079/C;3-HVAC Air Cooling Units Assembly (View) x 1
4	ITM-0056532/B;2-P70 Filter Box for ACU A/B x 1
4	ITM-0056533/B;2-P80 Filter Box for ACU C/D x 1
4	ITM-0056726/C;2-P70 ACU A Shut-off Damper Inlet x 1
4	ITM-0056734/C;2-P70 ACU B Shut-off Damper Inlet x 1
4	ITM-0067558/C;2-P80 ACU C Shut-off Damper Inlet x 1
4	ITM-0067559/C;2-P80 ACU D Shut-off Damper Inlet x 1
4	ITM-0038080/B;3-HVAC Control Panels Assembly (View) x 1
4	ITM-0070935/B;3-P70 HVAC UCP x 1
4	ITM-0070936/B;2-P80 HVAC UCP x 1
4	ITM-0020187/C;3-HVAC Ducting Assembly (View) x 1
4	ITM-0056421/B;2-P70 HPU FAN 1 x 1
4	ITM-0056422/B;2-P70 HPU FAN 2 x 1
4	ITM-0056423/B;2-P80 HPU FAN 3 x 1
4	ITM-0056424/B;2-P80 HPU FAN 4 x 1
4	ITM-0056429/A;2-P70 Fire Damper Inlet Air x 1
4	ITM-0056430/A;2-P80 Fire Damper Inlet Air x 1
4	ITM-0056431/A;2-P70 Fire Damper Outlet Air HPU Room x 1
4	ITM-0056432/A;2-P80 Fire Damper Outlet Air HPU Room x 1
4	ITM-0056433/A;2-P70 Fire Damper Outlet Air Air Lock x 1
4	ITM-0056434/A;3-P80 Fire Damper Outlet Air Air Lock x 1
4	ITM-0056498/A;3-P70 Fire Damper Control room/HPU room x 1
4	ITM-0056499/A;2-P80 Fire Damper Control room/HPU room x 1
4	ITM-0056500/B;2-P70 Balancing Damper Fresh Air VSD Room x 1
4	ITM-0056501/B;2-P80 Balancing Damper Fresh Air VSD Room x 1
4	ITM-0056502/B;2-P70 Balancing Damper Fresh Air Air Lock x 1
4	ITM-0056503/B;2-P80 Balancing Damper Fresh Air Air Lock x 1
4	ITM-0056504/A;2-P70 Duct Heater Air Lock x 1

Level	BOM Line
4	ITM-0056505/A;2-P80 Duct Heater Air Lock x 1
4	ITM-0056506/A;2-P70 Pressure Relief Damper Air Lock x 1
4	ITM-0056507/A;2-P80 Pressure Relief Damper Air Lock x 1
4	ITM-0056508/A;2-P70 Pressure Relief Damper HPU Room x 1
4	ITM-0056509/A;2-P80 Pressure Relief Damper HPU Room x 1
4	ITM-0056510/A;2-P70 Balancing Damper HPU Room x 1
4	ITM-0056511/A;2-P80 Balancing Damper HPU Room x 1
4	ITM-0063660/A;3-P70 Fire Damper Inergen Release VSD/Control Room x 1
4	ITM-0063661/A;2-P80 Fire Damper Inergen Release VSD/Control Room x 1
4	ITM-0063662/A;2-P70 Fire Damper Inergen Release HPU Room x 1
4	ITM-0063663/A;2-P80 Fire Damper Inergen Release HPU Room x 1
4	ITM-0070014/A;3-P70 Fire Damper Outlet Air VSD/Elec. Room x 1
4	ITM-0070015/A;2-P80 Fire Damper Outlet Air VSD/Elec. Room x 1
4	ITM-0070017/A;3-P70 HPU Room Air Inlet Balancing Damper x 1
4	ITM-0070018/A;3-P80 HPU Room Air Inlet Balancing Damper x 1
4	ITM-0075860/A;2-P70 ACU A/B Return Air Balancing Damper A x 1
4	ITM-0075861/A;2-P70 ACU A/B Return Air Balancing Damper B x 1
4	ITM-0075862/A;2-P70 ACU A/B Return Air Balancing Damper C x 1
4	ITM-0075863/A;2-P70 ACU A/B Return Air Balancing Damper D x 1
4	ITM-0075864/A;2-P80 ACU A/B Return Air Balancing Damper A x 1
4	ITM-0075865/A;2-P80 ACU A/B Return Air Balancing Damper B x 1
4	ITM-0075866/A;2-P80 ACU A/B Return Air Balancing Damper C x 1
4	ITM-0075867/A;2-P80 ACU A/B Return Air Balancing Damper D x 1
4	ITM-0094132/A;5-P70 HPU FAN 1 Shut Off Damper x 1
4	ITM-0094133/A;4-P70 HPU FAN 2 Shut Off Damper x 1
4	ITM-0094134/A;5-P80 HPU FAN 3 Shut Off Damper x 1
4	ITM-0094135/A;5-P80 HPU FAN 4 Shut Off Damper x 1
4	ITM-0040023/C;4-HVAC Piping and Tubing Assembly (View) x 1
4	ITM-0056727/A;1-P70 Balancing Valve PCM Water Outlet x 1
4	ITM-0056736/A;1-P80 Balancing Valve Water Outlet x 1
4	ITM-0067507/A;3-P70 Isolating Valve Water Inlet x 1
4	ITM-0067508/A;2-P70 Isolating Valve Water Outlet x 1
4	ITM-0067509/A;2-P80 Isolating Valve Water Inlet x 1
4	ITM-0067510/A;2-P80 Isolating Valve Water Outlet x 1
4	ITM-0067512/A;2-P70 VSD 1 Isolating Valve Water Inlet x 1
4	ITM-0067513/A;2-P70 VSD 1 Isolating Valve Water Outlet x 1
4	ITM-0067514/A;2-P70 VSD 2 Isolating Valve Water Inlet x 1
4	ITM-0067515/A;3-P70 VSD 2 Isolating Valve Water Outlet x 1
4	ITM-0067516/A;3-P80 VSD 3 Isolating Valve Water Inlet x 1
4	ITM-0067517/A;2-P80 VSD 3 Isolating Valve Water Outlet x 1
4	ITM-0067518/A;2-P80 VSD 4 Isolating Valve Water Inlet x 1
4	ITM-0067519/A;2-P80 VSD 4 Isolating Valve Water Outlet x 1
4	ITM-0083609/A;2-PCM P70 Pressure Regulator for Air to Fire Dampers x 1
4	ITM-0083610/A;2-PCM P70 Hand Operated Valve for Air to Fire Dampers x 1

Level	BOM Line
4	ITM-0083611/A;2-PCM P80 Pressure Regulator for Air to Fire Dampers x 1
4	ITM-0083612/A;2-PCM P80 Hand Operated Valve for Air to Fire Dampers x 1
4	ITM-0056723/A;1-P70 Balancing Valve VSD 1 x 1
4	ITM-0056724/A;1-P70 Balancing Valve VSD 2 x 1
4	ITM-0056732/A;1-P80 Balancing Valve VSD 3 x 1
4	ITM-0056733/A;1-P80 Balancing Valve VSD 4 x 1
4	ITM-0056526/C;4-P70 Air Indicators and Sensors Assembly (View) x 1
4	ITM-0056520/B;3-P70 ACU A Return Air Temperature Transmitter x 1
4	ITM-0056719/B;3-P70 ACU B Return Air Temperature Transmitter x 1
4	ITM-0083631/A;2-HPU Fan 1 Flow Switch x 1
4	ITM-0083632/A;2-HPU Fan 2 Flow Switch x 1
4	ITM-0083635/A;2-P70 HPU Room Temperature Transmitter x 1
4	ITM-0083637/A;2-P70 VSD Room Temperature Transmitter x 1
4	ITM-0083639/A;3-P70 VSD Room dP Transmitter x 1
4	ITM-0083641/A;2-P70 Air Lock Room dP Transmitter x 1
4	ITM-0083645/A;2-P70 Air Filter dP Indicator & Transmitter x 1
4	ITM-0083647/A;2-P70 VSD Room Pressure Gauge x 1
4	ITM-0083649/A;2-P70 VSD Room Temperature Gauge x 1
4	ITM-0083653/A;2-P70 Air Lock Room Pressure Gauge x 1
4	ITM-0083655/A;2-P70 Air Lock Room Temperature Gauge x 1
4	ITM-0056721/B;5-P70 Air Lock Room Temperature Switch For Duct Heater x 1
4	ITM-0083627/A;2-HPU Fan 1 Local Emergency Stop x 1
4	ITM-0083628/A;2-HPU Fan 2 Local Emergency Stop x 1
4	ITM-0056527/C;6-P80 Air Indicators and Sensors Assembly (View) x 1
4	ITM-0056522/B;3-P80 ACU C Return Air Temperature Transmitter (View) x 1
4	ITM-0056728/B;3-P80 ACU D Return Air Temperature Transmitter x 1
4	ITM-0083633/A;2-HPU Fan 3 Flow Switch x 1
4	ITM-0083634/A;2-HPU Fan 4 Flow Switch x 1
4	ITM-0083636/A;2-P80 HPU Room Temperature Transmitter x 1
4	ITM-0083638/A;2-P80 VSD Room Temperature Transmitter x 1
4	ITM-0083640/A;3-P80 VSD Room dP Transmitter x 1
4	ITM-0083642/A;2-P80 Air Lock Room dP Transmitter x 1
4	ITM-0083646/A;2-P80 Air Filter dP Indicator & Transmitter x 1
4	ITM-0083648/A;2-P80 VSD Room Pressure Gauge x 1
4	ITM-0083650/A;2-P80 VSD Room Temperature Gauge x 1
4	ITM-0083654/A;2-P80 Air Lock Room Pressure Gauge x 1
4	ITM-0083656/A;2-P80 Air Lock Room Temperature Gauge x 1
4	ITM-0056722/B;4-P80 Air Lock Room Temperature Switch For Duct Heater x 1
4	ITM-0083629/A;2-HPU Fan 3 Local Emergency Stop x 1
4	ITM-0083630/A;3-HPU Fan 4 Local Emergency Stop x 1
4	ITM-0056528/C;3-P70 Water Indicators and Sensors Assembly (View) x 1
4	ITM-0070937/A;2-P70 ACU A Water Detector x 1
4	ITM-0070938/A;2-P70 ACU B Water Detector x 1
4	ITM-0070941/A;2-P70 Piping Water Detector x 1

Level	BOM Line
4	ITM-0083657/A;2-P70 Water Inlet Temperature Gauge x 1
4	ITM-0083659/A;2-P70 Water Outlet Temperature Gauge x 1
4	ITM-0083661/A;2-P70 Water Inlet Pressure Gauge x 1
4	ITM-0083663/A;2-P70 Water Outlet Pressure Gauge x 1
4	ITM-0056529/C;3-P80 Water Indicators and Sensors Assembly (View) x 1
4	ITM-0070939/A;2-P80 ACU C Water Detector x 1
4	ITM-0070940/A;3-P80 ACU D Water Detector x 1
4	ITM-0070942/A;3-P80 Piping Water Detector x 1
3	ITM-0095968/A;3-SEC Assembly P70 (View) x 1
4	ITM-0089584/A;2-Safety Equipment Cabinet P70 x 1
3	ITM-0095969/A;4-SEC Assembly P80 (View) x 1
4	ITM-0089585/A;2-Safety Equipment Cabinet P80 x 1
3	ITM-0020500/A;3-BF outboard PCM connectors x 1
3	ITM-0038655/A;4-CF outboard PCM connectors x 1
2	ITM-0025365/B;3-Infield Jumpers (View) x 1
3	ITM-0020502/B;2-HV Electrical Flying Lead (View) x 12
4	ITM-0029849/B;3-HV WM FLYING LEAD PLUG TO PLUG R/A CONNECTORS
3	ITM-0020506/B;7-BF - Flying Lead (View) x 4
4	ITM-0055851/C;2-Hose Barrier Fluid
4	ITM-0094266/A;4-Walther Female Connector (R1) with Autoclave MP w/fishtail (View) x 2
4	ITM-0005923/B;2-ROV female connector stab R1 with Autoclave
3	ITM-0089693/B;2-Hydraulic Flying Lead P70/P80-CF-PU (View) x 4
4	ITM-0005924/B;2-ROV female connector stab R2 with Autoclave x 2
4	ITM-0077698/B;2-Control Fluid Hose
3	ITM-0052298/C;2-H#9 ETHERNET EFL x 8
3	ITM-0054652/C;2-H#10 SIGNAL EFL x 8
3	ITM-0052295/C;2-H#3 LV EFL x 4
3	ITM-0058985/D;1-H#4 OFL (View) x 4
4	ITM-0053563/D;1-FO TOPSIDE PROTECTIVE CAP FOR PLUG x 2
3	ITM-0056054/E;2-Type 1 HFL with Outboard MQC head x 2
3	ITM-0056055/E;2-Type 2 HFL with MQC head x 2
3	ITM-0056057/E;2-Type 3 HFL with MQC head
3	ITM-0087644/B;4-Stab Hot 43mm 1 port CV Super Duplex x 2
3	ITM-0093501/C;1-ROV Earth plug to plug jumper x 2
2	ITM-0025586/G;1-Tools and Skids (View) x 1
3	ITM-0020521/C;1-Dummy MPP Module (View) x 1
4	ITM-0081765/C;2-PRIMARY STEEL (View)
4	ITM-0099480/A;6-SOFT LANDING CYLINDER TF SL100/70-200 x 4
3	ITM-0020522/C;1-DUMMY PUMP UNIT ASSY (View) x 4
4	ITM-0093789/C;1-SECONDARY STRUCTURE DUMMY PUMP UNIT (View)
4	ITM-0057751/E;4-Destec female hub G8SBN-HD190 8" SCH 160 BW x 2
4	ITM-0094701/A;2-DIGITRON ROV RECEPTACLE CONNECTOR
4	ITM-0094839/A;2-WEPS-100 PT/TT SENSOR

Level	BOM Line
4	ITM-0117907/A;6-Harness #23 Cable 1.5m
4	ITM-0069944/C;1-H#23 DUMMY PUMP - JUMPER HARNESS W/SENSOR
4	ITM-0096152/C;1-Soft landing system SL100x270x300 x 2
4	ITM-0060930/B;3-destec clamp G8SB left handed
4	ITM-0060931/B;3-destec clamp G8SB right hand
3	ITM-0020525/B;1-ROV Subsea Storage Basket x 1
3	ITM-0020526/D;1-PUMP UNIT INSTALLATION TOOL (View) x 2
4	ITM-0068160/A;4-ACCUMULATOR ASSEMBLY 9060 (View) x 1
3	ITM-0020536/B;1-TEST AND TRANSPORT SKID SCM (View) x 1
3	ITM-0020538/A;7-Test SPCU Cabinet (View)
4	ITM-0065849/A;6-Topside Fiber Optical Modem - Focal 922 Assembly (View) x 2
4	ITM-0056151/A;7-Topside Fiber Optical Modem - Focal 922
4	ITM-0069149/A;7-CONNECTOR HARNESS, 37-PIN MICRO D, MALE MIN-E-CON 72.0 INCH, FOCAL 922 MODEM
3	ITM-0020542/D;1-FL DEPLOYMENT FRAMES FOR P70/P80 (View) x 1
4	ITM-0108001/C;1-1- FL Deployment Frame
4	ITM-0108002/C;1-2- FL Deployment Frame
4	ITM-0108003/C;1-3- FL Deployment Frame
4	ITM-0108004/C;1-4- FL Deployment Frame
4	ITM-0108005/C;1-5- FL Deployment Frame
4	ITM-0108006/C;1-6- FL Deployment Frame
4	ITM-0108007/C;1-7- FL Deployment Frame
3	ITM-0081689/C;2-Flying Lead Orientation Tool x 2
3	ITM-0064253/D;2-Choke Insert Running Tool (View) x 2
3	ITM-0064280/D;2-Choke Insert Running Tool Shipping Skid x 2
3	ITM-0064254/D;3-Choke Insert Transport and Workover Skid x 1
3	ITM-0097496/A;5-Laptop for HVAC UCP
3	ITM-0096345/A;3-SCM Transport skid final assembly (View) x 2
3	ITM-0081096/B;1-SCM INSTALLATION TOOL (View)
4	ITM-0082534/A;2-SOFT LANDING CYLINDER 60-200 x 2
3	ITM-0112816/D;1-PU IT SIMPLIFIED (View) x 2
2	ITM-0020516/K;1-SUPPORT AND LEVELING STRUCTURE P80 - ASSEMBLY DRAWING (View) x 1
3	ITM-0057752/I;1-SUPPORT AND LEVELING STRUCTURE - WELDING DRAWING SECONDARY STEEL (View)
4	ITM-0057753/J;1-SUPPORT AND LEVELING STRUCTURE - WELDING DRAWING PRIMARY STEEL (View)
3	ITM-0113295/B;1-MPP MODULE GUIDE POST (LONG) - ROV BOTTOM RELEASABLE
3	ITM-0113296/C;1-MPP MODULE GUIDE POST (SHORT) - ROV BOTTOM RELEASABLE
3	ITM-0083506/A;4-HANGOFF PLATE x 4
3	ITM-0042712/C;8-STAB RECEPTACLE (View) x 4
3	ITM-0076174/B;2-STABCON MOUNTING PLATE (View) x 4
2	ITM-0020515/C;1-FOUNDATION - ASSEMBLY DRAWING (View) x 2
3	ITM-0057803/H;1-FOUNDATION - WELDING DRAWING SECONDARY STEEL (View) x 1
4	ITM-0057804/J;1-FOUNDATION - WELDING DRAWING PRIMARY STEEL (View)

Level	BOM Line
4	ITM-0058609/D;2-RETAINMENT BOLT FIXED
4	ITM-0058608/D;2-REATAINMENT BOLT FREE
4	ITM-0075633/F;1-IMENCO GUIDE PIN RECEPTACLE - SUPPORT (View) x 2
4	ITM-0059403/E;1-FOUNDATION VENTING HATCH (View) x 2
4	ITM-0059404/D;1-ASSEMBLY DRAWING - FOUNDATION VENTING HATCH (View)
3	ITM-0081134/E;2-SUPPORT AND LEVELING STRUCTURE GUIDE POST (LONG) - ROV TOP RELEASABLE (View)
3	ITM-0081136/E;1-SUPPORT AND LEVELING STRUCTURE GUIDE POST (SHORT) - ROV TOP RELEASABLE
3	ITM-0087120/B;2-ONSHORE LIFTING SLINGS - FOUNDATION (View)
4	ITM-0077692/A;2-SLING LOW x 4
4	ITM-0011962/A;2-LIFT RING x 3
4	ITM-0081507/A;5-CROSBY WIDE BODY SHACKLE - 125T (View) x 4
4	ITM-0116523/A;3-ROV SHACKLE
4	ITM-0085698/B;1-BULL'S EYE PROTECTION (View)
2	ITM-0020501/A;3-Operator Training Station (View) x 1
3	ITM-0090961/A;14-OTS - Operator Station x 2
3	ITM-0090962/A;4-OTS - Instructor Station x 1
2	ITM-0048178/B;2-SDU Connectors, parkings, caps (View) x 1
3	ITM-0056060/D;2-Parking receptacle x 4
3	ITM-0056053/D;2-Inboard MQC Head with 2 Male Couplers (SDU 80) (View) x 2
3	ITM-0056059/D;2-Long Term Protection for Male 2 Ports Plate x 2
3	ITM-0056058/D;2-Long Term Protection Caps for Male 4 Ports Plate x 2
3	ITM-0056051/D;2-Inboard MQC Head with 4 Male Couplers (SDU 70) (View) x 2
3	ITM-0056643/D;2-Outboard Test Plate x 4
3	ITM-0003702/A;5-ROV male connector receptacle R1 with weld tail (S Duplex) (View) x 4
3	ITM-0003687/B;2-ROV connector parking receptacle R0 x 4
3	ITM-0056825/C;3-H#18 ROV PARKING DUMMY PLUG x 6
3	ITM-0052277/C;3-H#1 LV UMBILICAL TERMINATION ROV PLUG x 6
3	ITM-0073920/C;1-H#27 FO ROV PARKING DUMMY RECEPTACLE x 12
3	ITM-0073362/B;2-H#19 ROV FLYING DUMMY RECEPTACLE x 6
3	ITM-0058984/D;1-H#2 FO UMBILICAL TERMINATION JUMPER HARNESS x 6
3	ITM-0058987/C;2-H#25 FO ROV FLYING DUMMY PLUG - LOOPED LTFC x 14
3	ITM-0009574/C;6-Parking connector HV x 16
3	ITM-0060317/A;4-ROV RECEPTACLE CONNECTOR x 2
3	ITM-0060349/B;3-ROV TEST DUMMY PLUG FOR SWIMMER SYSTEM x 3
3	ITM-0060360/B;2-ROV TOPSIDE TEST PLUG
3	ITM-0060361/A;6-ROV PARKING RECEPTACLE CONNECTOR x 2
3	ITM-0093500/D;1- Earth receptacle connector x 2
3	ITM-0084256/B;1-SDU Power Jumper 3 Slot Receptacle Assembly Drawing (View) x 4
3	ITM-0093722/A;2-4 Slot Power Jumper Parking Receptacle Assembly Drawing (View) x 4
3	ITM-0006373/C;2-ROV connector plug R0 with fishtail (View) x 4
3	ITM-0003693/C;3-ROV connector plug R0 dummy female

Level	BOM Line
3	ITM-0003694/C;2-ROV connector plug R0 releasable x 4
3	ITM-0029851/C;2-HV WM PLUG TYPE TEST CONNECTOR (View) x 7
3	ITM-0013094/C;2-TEST - ROV TEST RECEPTACLE W/PIGTAIL
3	ITM-0060291/D;2-Spectron 8 UTU - ROV RECEPTACLE x 2
3	ITM-0113422/A;5-Stab Plate - Connector Assembly (View) x 14
3	ITM-0003692/C;2-ROV female connector stab R1 with JIC x 4
3	ITM-0056061/D;3-Parking temporary protective cover x 4
3	ITM-0071787/C;1-H#28 TEST - FO ROV FLYING PLUG W/HOSE AND BOX (View) x 7
3	ITM-0053563/D;1-FO TOPSIDE PROTECTIVE CAP FOR PLUG x 1
3	ITM-0128150/A;4-Swimmer Topside Test Plug
3	ITM-0024728/C;2-TEST - ROV TEST RECEPTACLE W/PIGTAIL x 3
3	ITM-0076470/A;2-STAB PLATE ASSEMBLY (View) x 2
3	ITM-0106964/B;1-Parking Receptacle Subsea for Earth Plug Connector x 2
3	ITM-0106965/B;3-Protection Plug Subsea for Earth Receptacle Connector x 2
2	ITM-0038653/C;1-Test Equipment (View) x 1
3	ITM-0037077/B;2-Test HPU CF x 1
3	ITM-0037078/B;2-Test HPU BF x 1
3	ITM-0020530/A;1-Test Equipment
3	ITM-0020538/A;7-Test SPCU Cabinet (View)
3	ITM-0065849/A;6-Topside Fiber Optical Modem - Focal 922 Assembly (View) x 2
3	ITM-0056151/A;7-Topside Fiber Optical Modem - Focal 922
3	ITM-0069149/A;7-CONNECTOR HARNESS, 37-PIN MICRO D, MALE MIN-E-CON 72.0 INCH, FOCAL 922 MODEM
3	ITM-0016573/B;2-IXXAT CANopen Device Manager x 1
3	ITM-0069673/A;4-IXXAT USB-to-CAN II interface - Automotive Version x 1
3	ITM-0029851/C;2-HV WM PLUG TYPE TEST CONNECTOR (View)
3	ITM-0071787/C;1-H#28 TEST - FO ROV FLYING PLUG W/HOSE AND BOX (View) x 2
3	ITM-0053563/D;1-FO TOPSIDE PROTECTIVE CAP FOR PLUG x 1
3	ITM-0082750/A;1-Win Server 2012 Standard x 1
3	ITM-0083852/A;1-Microsoft Windows 8 Pro x 1
3	ITM-0083853/A;1-WinPro SNGL Upgrade to virtuell x 1
3	ITM-0082749/A;1-Office Pro Plus 2013 SNGL OLP NL x 1
3	ITM-0096285/A;2-Factory Talk Gateway 5000 Tags SW x 1
3	ITM-0011889/C;2-Factory Talk View SE Server 100 displays SW x 1
3	ITM-0011890/C;2-Factory Talk View SE Client SW x 1
3	ITM-0011891/B;3-RS Logix Service Edition SW x 1
3	ITM-0016179/A;10-Canary TLEH 1000 Historian & 2x Trendlink SW x 1
3	ITM-0096281/A;2-Canary Trend Historian 500 Tags SW x 1
3	ITM-0122981/A;2-O-Ring Back Seal 234ID*3.5Dia x 50
3	ITM-0073919/C;1-H#29 TEST - FO ROV BULKHEAD RECEPTACLE W/HOSE AND BOX (View) x 2
3	ITM-0071816/C;1-FO TOPSIDE PROTECTIVE CAP FOR RECEPTACLE x 1
3	ITM-0056794/C;3-H#36 TEST - ROV PLUG W/HOSE & PIGTAIL x 2
3	ITM-0024930/C;2-TEST - ROV TEST PLUG W/PIGTAIL x 2

Level	BOM Line
3	ITM-0013094/C;2-TEST - ROV TEST RECEPTACLE W/PIGTAIL x 2
3	ITM-0024728/C;2-TEST - ROV TEST RECEPTACLE W/PIGTAIL x 2
3	ITM-0052748/D;1-TEST - EROV TEST PLUG W/PIGTAIL x 2
3	ITM-0052740/D;1-TEST - EROV TEST RECEPTACLE W/PIGTAIL
3	ITM-0056642/D;3-Inboard Test Plate x 2
3	ITM-0056643/D;2-Outboard Test Plate x 2
3	ITM-0094256/B;1-Walter Female Connector (R1) with JIC w/fishtail (View) x 2
3	ITM-0003692/C;2-ROV female connector stab R1 with JIC
3	ITM-0094273/A;3-Walther Female Connector (R2) with JIC w/fishtail (View) x 2
3	ITM-0003695/B;2-ROV female connector stab R2 with JIC
3	ITM-0003696/B;3-ROV male connector receptacle R2 with JIC x 2
3	ITM-0003691/C;2-ROV male connector receptacle R1 with JIC x 2
2	ITM-0074472/A;8-Flow Line Equipment (View) x 1
3	ITM-0052308/B;2-M801 Outboard hub. Transportation frame. (View)
3	ITM-0049341/C;1-Term.Head KC4-10, ID6+2+8HL, S1
3	ITM-0042436/C;5-CAP INBOARD LPE, KC4-10, ID8 x 12
3	ITM-0049325/C;2-Belly Clamp x 10
3	ITM-0042709/C;3-Outboard Hub Prot. Cap, KC4-10 x 10
3	ITM-0049319/B;9- Termination Head KC4.2-10, ID8, Stabcon MK1 x 8
3	ITM-0042708/C;6-Termination Head KC4-10, ID8, Stabcon MK1 x 2
3	ITM-0049329/B;8-Lifting Frame for 21 hour Insulation Cap (View) x 4
3	ITM-0049321/B;5-Transportation frames for termination heads (View) x 10
3	ITM-0049346/B;7-Stab adjustment jig Receptacle adjustment jig in FE specification).
3	ITM-0049328/B;3-Transportation frame for Belly Clamps (View) x 5
3	ITM-0042710/C;5-Test Cap Outb. (HP), KC4-10, ID6/8 x 10
3	ITM-0042711/D;2-CAP, INSULATION, REINST., KC4.2-10, LARGE TYPE, MANIFOLD SIDE, GA x 10
3	ITM-0049331/B;3-Seals and gaskets; Installation seals (View) x 13
3	ITM-0042713/C;2-Seals and gaskets; Test seals x 56
3	ITM-0052309/B;2-Dummy frame for CAT Interface test.
3	ITM-0042438/C;18-Cap Inboard Test & Flushing (HP), KC4-10, ID8 x 8
3	ITM-0042707/C;10- Flowing Test Cap, KC4-10, ID8 x 4
3	ITM-0049327/B;7-Basket, Insert F/ Insulation Cap (View) x 10
3	ITM-0096126/B;2-Lifting Yoke x 4
3	ITM-0105602/A;2-LP CAP MeOH Termination Head
3	ITM-0114583/B;1-Outboard HP Cap
3	ITM-0112477/B;2-ROV Tool, Torque, clutch
3	ITM-0110628/A;2-Insulation, split seal
2	ITM-0089583/A;4-PCM Foam Deluge Skid x 1
2	ITM-0080221/D;1-SUPPORT AND LEVELING STRUCTURE P70 – ASSEMBLY DRAWING (View) x 1
3	ITM-0057753/J;1-SUPPORT AND LEVELING STRUCTURE - WELDING DRAWING PRIMARY STEEL (View)
3	ITM-0057752/I;1-SUPPORT AND LEVELING STRUCTURE - WELDING DRAWING SECONDARY STEEL (View)

Level	BOM Line
4	ITM-0057753/J;1-SUPPORT AND LEVELING STRUCTURE - WELDING DRAWING PRIMARY STEEL (View)
3	<i>ITM-0113295/B;1-MPP MODULE GUIDE POST (LONG) - ROV BOTTOM RELEASABLE</i>
3	<i>ITM-0113296/C;1-MPP MODULE GUIDE POST (SHORT) - ROV BOTTOM RELEASABLE</i>
3	<i>ITM-0083506/A;4-HANGOFF PLATE x 4</i>
3	<i>ITM-0042712/C;8-STAB RECEPTACLE (View) x 4</i>
3	<i>ITM-0076174/B;2-STABCON MOUNTING PLATE (View) x 4</i>
2	ITM-0038654/A;9-Operator Work Station (OWS) (View) x 1
3	<i>ITM-0032875/D;3-Server SuperMicro CSE-825 Short (View) x 1</i>
3	<i>ITM-0046529/A;3-Optical Mouse x 1</i>
3	<i>ITM-0046533/A;5-Keyboard x 1</i>
3	<i>ITM-0052474/A;2-Symantec Endpoint Protection x 1</i>
3	<i>ITM-0080228/A;1-Monitor Fujitsu 19" 1280x1024 x 2</i>
3	<i>ITM-0082751/A;1-Windows 7 Ultimate x 1</i>
3	<i>ITM-0082752/A;1-Chief dual vertical monitor table stand x 1</i>
3	<i>ITM-0083848/A;1-Supermicro Front Bezel Cover x 1</i>
3	<i>ITM-0082641/A;1-KVM unit_cl5708 x 2</i>
3	<i>ITM-0082806/A;1-KVM Cable USB x 2</i>
3	<i>ITM-0080234/A;1-Media Converter, Black Box x 2</i>
3	<i>ITM-0084641/A;2-Patch Cable x 2</i>
3	<i>ITM-0084640/A;1-RJ45 Cable x 4</i>
3	<i>ITM-0084644/A;1-VGA Cable x 2</i>
3	<i>ITM-0084642/A;2-Patch Panel x 1</i>
3	<i>ITM-0084645/A;2-Powerbar x 1</i>
3	<i>ITM-0084639/A;1-Graphic Card, dual screen x 1</i>
3	<i>ITM-0084651/A;1-Shelf x 1</i>
3	<i>ITM-0038134/A;11-Fiber Optic Cable x 1</i>
3	<i>ITM-0096143/A;2-KVM Extender x 1</i>
2	ITM-0020519/C;2-MPP MODULE P70 w/retrievable (View) x 1
3	<i>ITM-0057559/E;3-MPP MODULE (P70) ASSEMBLY (View)</i>
4	ITM-0057039/F;2-MPP MODULE - WELDING DRAWING SECONDARY STEEL (View)
4	ITM-0057041/F;2-MPP MODULE - PRIMARY STEEL WELDING DRAWING (View)
4	ITM-0060304/A;2-SCM Mounting Base Assembly (View)
4	ITM-0052300/D;2-H#12 ETHERNET JUMPER (View) x 2
4	ITM-0034188/D;2-H#20 JUMPER HARNESS W/SENSOR (View) x 1
4	ITM-0034189/D;2-H#21 JUMPER HARNESS W/SENSOR (View) x 2
4	ITM-0052301/E;2-H#22 JUMPER W/ODI CONNECTOR (View) x 2
4	ITM-0081753/B;2-H#32 ETHERNET JUMPER (View) x 2
4	ITM-0081757/B;5-H#33 JUMPER HARNESS W/SENSOR (View) x 1
4	ITM-0056826/D;2-H#16 ROV PARKING RECEPTACLE x 8
4	ITM-0077951/A;2-BRACKET FOR JUNCTION BOX (View) x 8
4	ITM-0081756/A;2-H#12 ETHERNET JUMPER - PHANTOM (View)
4	ITM-0081758/A;2-H#21 JUMPER HARNESS W/SENSOR - PHANTOM (View)
4	ITM-0083827/A;2-H#22 JUMPER W/ODI CONNECTOR - PHANTOM (View)

Level	BOM Line
4	ITM-0081754/A;2-H#32 ETHERNET JUMPER - PHANTOM (View)
4	ITM-0087014/A;3-SOFT LANDING CYLINDER x 4
3	ITM-0025652/G;1-PUMPUNIT ASSEMBLY (View) x 2
4	ITM-0056111/D;1-PUMPUNIT - WELDING DRAWING SECONDARY STEEL (View)
4	ITM-0071600/E;4-MPFM - GA DRAWING 9060 - GIRRI PW Vx SS TYPE 4. 88U (View)
4	ITM-0085727/B;1-PUMP UNIT ROOF STRUCTURE
4	ITM-0052299/C;2-H#11 ETHERNET JUMPER x 2
3	ITM-0020520/E;1-GirRI SCM (View)
4	ITM-0055657/B;1-SCM Internal assembly
3	ITM-0073879/B;2-V81 - Chemical Throttle Valve (View) x 2
3	ITM-0067141/B;2-MINIMUM FLOW VALVE INSERT x 2
2	ITM-0051128/B;1-MPP MODULE P80 w/retrievable (View) x 1
3	ITM-0069112/D;1-MPP MODULE (P80) ASSEMBLY (View)
4	ITM-0057039/F;2-MPP MODULE - WELDING DRAWING SECONDARY STEEL
4	ITM-0057041/F;2-MPP MODULE - PRIMARY STEEL WELDING DRAWING
4	ITM-0060304/A;2-SCM Mounting Base Assembly (View)
4	ITM-0052300/D;2-H#12 ETHERNET JUMPER (View) x 2
4	ITM-0034188/D;2-H#20 JUMPER HARNESS W/SENSOR (View) x 1
4	ITM-0034189/D;2-H#21 JUMPER HARNESS W/SENSOR (View) x 2
4	ITM-0052301/E;2-H#22 JUMPER W/ODI CONNECTOR (View) x 2
4	ITM-0081753/B;2-H#32 ETHERNET JUMPER (View) x 2
4	ITM-0081757/B;5-H#33 JUMPER HARNESS W/SENSOR (View) x 1
4	ITM-0056826/D;2-H#16 ROV PARKING RECEPTACLE x 8
4	ITM-0077951/A;2-BRACKET FOR JUNCTION BOX (View) x 8
4	ITM-0081756/A;2-H#12 ETHERNET JUMPER - PHANTOM (View)
4	ITM-0081758/A;2-H#21 JUMPER HARNESS W/SENSOR - PHANTOM
4	ITM-0083827/A;2-H#22 JUMPER W/ODI CONNECTOR - PHANTOM
4	ITM-0081754/A;2-H#32 ETHERNET JUMPER - PHANTOM (View)
4	ITM-0087014/A;3-SOFT LANDING CYLINDER x 4
3	ITM-0025652/G;1-PUMP UNIT ASSEMBLY (View) x 2
4	ITM-0056111/D;1-PUMP UNIT - WELDING DRAWING SECONDARY STEEL
5	ITM-0023221/F;1-Pump Multiphase type 5FA5GD
4	ITM-0071600/E;4-MPFM - GA DRAWING 9060 - GIRRI PW Vx SS TYPE 4. 88U
4	ITM-0085727/B;1-PUMP UNIT ROOF STRUCTURE
4	ITM-0052299/C;2-H#11 ETHERNET JUMPER x 2
3	ITM-0020520/E;1-GirRI SCM (View)
4	ITM-0055657/B;1-SCM Internal assembly
3	ITM-0073879/B;2-V81 - Chemical Throttle Valve (View) x 2
3	ITM-0067141/B;2-MINIMUM FLOW VALVE INSERT x 2

1.6 Subsea MPP system

CENTRIFUGAL PUMP API 610 10TH EDITION / ISO 13709 PROCESS DATA SHEET SI UNITS

PAGE **2** OF **6**

JOB NO. _____ ITEM NO.(S) _____
 REQ. / SPEC. NO. **I**
 PURCH. ORDER NO. **TEPA-GIR-2011-C200** DATE **04-Nov-2014**
 INQUIRY NO. _____ BY _____

1 APPLICABLE TO: ☐ PROPOSALS ☐ PURCHASE ☒ AS BUILT																																																														
2 FOR TOTAL				UNIT ITM-0023221																																																										
3 SITE Girri				SERVICE Multiphase Flow																																																										
4 NOTES: INFORMATION BELOW TO BE COMPLETED: ☐ BY PURCHASER ☐ BY MANUFACTURER ☒ BY MANUFACTURER OR PURCHASER																																																														
5 ☐ DATA SHEETS																																																														
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th colspan="6"></th> <th colspan="2">REVISIONS</th> </tr> <tr> <th>ITEM NO.</th> <th>ATTACHED</th> <th>ITEM NO.</th> <th>ATTACHED</th> <th>ITEM NO.</th> <th>ATTACHED</th> <th>NO.</th> <th>DATE</th> <th>BY</th> </tr> <tr> <td>7 PUMP</td> <td>☐</td> <td></td> <td>☐</td> <td></td> <td>☐</td> <td>1</td> <td></td> <td></td> </tr> <tr> <td>8 MOTOR</td> <td>☐</td> <td></td> <td>☐</td> <td></td> <td>☐</td> <td>2</td> <td></td> <td></td> </tr> <tr> <td>9 GEAR</td> <td>☐</td> <td></td> <td>☐</td> <td></td> <td>☐</td> <td>3</td> <td></td> <td></td> </tr> <tr> <td>10 TURBINE</td> <td>☐</td> <td></td> <td>☐</td> <td></td> <td>☐</td> <td>4</td> <td></td> <td></td> </tr> </table>																REVISIONS		ITEM NO.	ATTACHED	ITEM NO.	ATTACHED	ITEM NO.	ATTACHED	NO.	DATE	BY	7 PUMP	☐		☐		☐	1			8 MOTOR	☐		☐		☐	2			9 GEAR	☐		☐		☐	3			10 TURBINE	☐		☐		☐	4		
						REVISIONS																																																								
ITEM NO.	ATTACHED	ITEM NO.	ATTACHED	ITEM NO.	ATTACHED	NO.	DATE	BY																																																						
7 PUMP	☐		☐		☐	1																																																								
8 MOTOR	☐		☐		☐	2																																																								
9 GEAR	☐		☐		☐	3																																																								
10 TURBINE	☐		☐		☐	4																																																								
11 APPLICABLE OVERLAY STANDARD(S):																																																														
12 ☐ OPERATING CONDITIONS (5.1.3)																																																														
13 FLOW, NORMAL (m³/h) RATED 453 (m³/h)																																																														
14 OTHER @ GVF = 53% (Note 1)																																																														
15 SUCTION PRESSURE MAX./RATED 9.4 / 4.7 (MPa)																																																														
16 DISCHARGE PRESSURE 13.5 (Note 1) (MPa)																																																														
17 DIFFERENTIAL PRESSURE 8.8 (Note 1) (MPa)																																																														
18 DIFF. HEAD (m) NPSHA (m)																																																														
19 PROCESS VARIATIONS (5.1.4)																																																														
20 STARTING CONDITIONS (5.1.4)																																																														
21 SERVICE: ☒ CONT. ☐ INTERMITTENT (STARTS/DAY)																																																														
22 ☐ PARALLEL OPERATION REQ'D (5.1.13)																																																														
23 ☐ SITE DATA (5.1.3)																																																														
24 LOCATION: (5.1.30)																																																														
25 ☐ INDOOR ☐ HEATED ☐ OUTDOOR ☐ UNHEATED																																																														
26 ☐ ELECTRICAL AREA CLASSIFICATION (5.1.24 / 6.1.4)																																																														
27 CL GR DIV																																																														
28 ☐ WINTERIZATION REQ'D ☐ TROPICALIZATION REQ'D																																																														
29 SITE DATA (5.1.30)																																																														
30 ☐ ALTITUDE -1450 (m) BAROMETER NA (MPa)																																																														
31 ☐ RANGE OF AMBIENT TEMPS: MIN./MAX. 3.8 / 4.4 (°C)																																																														
32 ☐ RELATIVE HUMIDITY: MIN. / MAX. NA / NA (%)																																																														
33 UNUSUAL CONDITIONS: (5.1.30) ☐ DUST ☐ FUMES																																																														
34 ☒ OTHER SUBSEA APPLICATION																																																														
35																																																														
36																																																														
37 ☐ DRIVER TYPE																																																														
38 ☒ INDUCTION MOTOR ☐ STEAM TURBINE ☐ GEAR																																																														
39 ☐ OTHER																																																														
40																																																														
41 ☐ MOTOR DRIVER (6.1.1 / 6.1.4)																																																														
42 ☒ MANUFACTURER FRAMO / LOHER (Note 2 and Note 12)																																																														
43 ☐ 2900 (kW) ☐ 4252 (r/min)																																																														
44 ☐ FRAME FR355 ☒ ENCLOSURE 346 bar dp																																																														
45 ☒ HORIZONTAL ☒ VERTICAL ☒ SERVICE FACTOR S9																																																														
46 ☒ VOLTS/PHASE/HERTZ 6000/6600 / 3 / 71.5																																																														
47 ☐ TYPE Two pole induction motor																																																														
48 ☐ MINIMUM STARTING VOLTAGE (6.1.5)																																																														
49 ☒ INSULATION 11 kV ☐ TEMP. RISE B																																																														
50 ☐ FULL LOAD AMPS 340 A																																																														
51 ☒ LOCKED ROTOR AMPS NA																																																														
52 ☒ STARTING METHOD Frequency drive																																																														
53 ☒ LUBE Barrier oil (Note 7)																																																														
54																																																														
54 BEARINGS (TYPE/NUMBER):																																																														
55 ☐ RADIAL Waukesha Tilt pad / 2																																																														
56 ☐ THRUST Waukesha Tilt pad / 1																																																														
57 ☐ VERTICAL THRUST CAPACITY																																																														
58 UP 0 (N) DOWN 45000 (N)																																																														
59																																																														
60																																																														
61 ☐ LIQUID (5.1.3)																																																														
62 LIQUID TYPE OR NAME OIL, GAS AND WATER																																																														
63 ☒ HAZARDOUS ☒ FLAMMABLE ☐ (5.1.5)																																																														
<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <th>MIN.</th> <th>NORMAL</th> <th>MAX.</th> </tr> <tr> <td>4</td> <td>61.7 - 67.4</td> <td>93 (Note 1)</td> </tr> </table>										MIN.	NORMAL	MAX.	4	61.7 - 67.4	93 (Note 1)																																															
MIN.	NORMAL	MAX.																																																												
4	61.7 - 67.4	93 (Note 1)																																																												
64 PUMPING TEMP (°C)																																																														
65 VAPOUR PRESS. (MPa)																																																														
66 RELATIVE DENSITY (SG): 0.46 0.46 - 0.92 1.0 (Note 1 and 8)																																																														
67 VISCOSITY (mPa-s) 0.8 0.8 - 2.6 2.6 (Note 1)																																																														
68 SPECIFIC HEAT, Cp (kJ/kg-K)																																																														
69 ☐ CHLORIDE CONCENTRATION (6.5.2.4) (mg/kg)																																																														
70 ☐ H₂S CONCENTRATION (mol fraction) WET (5.12.1.12c)																																																														
71 CORROSIVE / EROSION AGENT (5.12.1.9)																																																														
72																																																														
73 MATERIALS (5.12.1.1)																																																														
74 ☐ ANNEX H CLASS (5.12.1.1)																																																														
75 ☐ MIN DESIGN METAL TEMP (5.12.4.1) (°C)																																																														
76 ☐ REDUCED-HARDNESS MATERIALS REQ'D. (5.12.1.12)																																																														
77 ☐ BARREL/CASE 22% Cr Duplex IMPELLER 22% Cr Duplex +TC coating																																																														
78 ☐ CASE/IMPELLER WEAR RINGS TC coating (Note 3)																																																														
79 ☐ SHAFT 34 Cr Ni Mo6																																																														
80 ☐ DIFFUSERS 22% Cr Duplex																																																														
81																																																														
82 PERFORMANCE:																																																														
83 PROPOSAL CURVE NO. Note 9 ☐ max. 4600 r/min																																																														
84 ☐ IMPELLER DIA. RATED 320 MAX. MIN. (mm)																																																														
85 ☐ IMPELLER TYPE Helico-Axial - 10 stages																																																														
86 ☐ RATED POWER 2500 kW (kW) EFFICIENCY (%)																																																														
87 ☐ MINIMUM CONTINUOUS FLOW:																																																														
88 THERMAL (m³/h) STABLE 120 at 1500 RPM (m³/h)																																																														
89 ☐ PREFERRED OPER. REGION TO (m³/h)																																																														
90 ☐ ALLOWABLE OPER. REGION TO (m³/h)																																																														
91 ☐ MAX. HEAD @ RATED IMPELLER (m)																																																														
92 ☐ MAX. POWER @ RATED IMPELLER (kW)																																																														
93 ☐ NPSHR AT RATED FLOW (m) (5.1.10)																																																														
94 ☒ MAX. SUCTION SPECIFIC SPEED: (5.1.11)																																																														
95 ☒ MAX. SOUND PRESS. LEVEL REQ'D NA (dBA) (5.1.16)																																																														
96 ☒ EST. MAX. SOUND PRESS. LEVEL NA (dBA) (5.1.16)																																																														
97 ☒ EST. MAX. SOUND POWER LEVEL NA (dBA) (5.1.16)																																																														
98 ☐ UTILITY CONDITIONS (5.1.3)																																																														
99 ELECTRICITY																																																														
100 DRIVERS																																																														
101 HEATING																																																														
102 SYSTEM VOLTAGE DIP ☐ 80% ☐ OTHER (6.1.5)																																																														
103																																																														
104 STEAM																																																														
105 DRIVERS																																																														
106 HEATING																																																														
107 COOLING WATER: (5.1.19) SOURCE Sea																																																														
108 SUPPLY TEMP. 4 (°C) MAX. RETURN TEMP. (°C)																																																														
109 NORM. PRESS. (MPa) DESIGN PRESS. (MPa)																																																														
110 MIN. RET. PRESS. (MPa) MAX. ALLOW. D.P. (MPa)																																																														
111 CHLORIDE CONCENTRATION: (mg/kg)																																																														

1.7 Scope of supply

H

A

NOTES:

NOTE 1: For External JB, Ducting and Dampers equipment, please see specific drawings given under references.

Item	Service Description
1	PCM P70
2	Inergen Bottleneck
3	Safety Equipment Cabinet
4	Stretchier
5	MCC 1
6	LV 1
7	SPCU 1
8	UCP 1
9	HVAC UCP 1
10	VSD P70R
11	VSD P70L
12	VSD P70R Input Transformer
13	VSD P70L Input Transformer
14	VSD P80L Output Transformer
15	Barrier Fluid Purifier
16	Barrier Fluid HPU
17	Control Fluid HPU
18	ACU A
19	ACU B


REFERENCE:

AO-050-GTO-311-000180 PCM P70/P80 GA EXTERNAL
AO-050-GTO-311-000185 PCM P70/P80 LIFT, ARR. AND COG
AO-050-GTO-332-000064 PCM - HVAC O&D
AO-050-GTO-310-000006 PCM - SAFETY PLOT PLAN


ABBREVIATIONS

FLOT - Flying Lead Orientation Tool
MFCV - Minimum Flow Control Valve
FL - Flying Lead
LV - Low Voltage
HV - High Voltage
SCM - Subsea Control Module
SCPS - Subsea Control Panel Station
PDS - Power Distribution System
MCC - Motor Control Center
HPU - Hydraulic Power Unit
CF - Control Fluid
BF - Barrier Fluid
MCC - Multi Quick Connector
LQC - Low Quick Connector
LV - LV Connector
FO - Fiber Optic
EL - Small Power

Item	Service Description
101	PCM P80
102	Inergen Bottleneck
103	Safety Equipment Cabinet
104	Stretchier
105	MCC 2
106	LV 2
107	SPCU 2
108	UCP 2
109	HVAC UCP 2
110	VSD P80R
111	VSD P80L
112	VSD P80R Input Transformer
113	VSD P80L Input Transformer
114	VSD P80R Output Transformer
115	Barrier Fluid Nitrogen Booster Pump
116	Barrier Fluid HPU
117	Control Fluid HPU
118	ACU C
119	ACU D



PLAN VIEW PCM P70




PLAN VIEW PCM P80

Tooling:

- Trolleys for Inergen bottles
- Trolleys for HPU accumulators
- VSD: maintenance platform and trolley for handling VSD cells
- Flexible hoses for HPU maintenance
- Tooling for HVAC balancing valve adjustment
- SPCU
- OTS

General Equipment:

- Inergen Equipment panels
- Vesda System
- Engineering Work Stations
- Operator Training Station
- Operator Work Stations
- Emergency Lighting
- UPS PCM
- AUX PCM
- PAGA-SYSTEM A
- PAGA-SYSTEM B
- TELEPHONE
- Auxiliary Equipment
- Topside Tests Equipments
- PCM Load out rigging and Spreader Bar
- Lighting and small power PCM
- F&G Detection Equipment



PCM FOAM SKID SIDE VIEW



PCM FOAM SKID TOP VIEW

Rev	Date	Status	Revised By	Checked By	Approved By
01	20/04/2015	ASB	As Built		
02	19/04/2015	AFC	Accepted for Construction	ATR	SMA
03	19/04/2014	AFC	Accepted for Construction	HA	TWO
04	28/07/2013	FA	Issued for Approval	HA	TWO
05	04/04/2012	FR	Issued for Review	BSU	FA




This document is the property of TOTAL E&P. It is not to be distributed outside the authorized personnel of TOTAL E&P.

Scope of Supply, CPY

Doc Type	Signature	Signature	Signature	Signature
DRW	04	SPS	SPS	SPS
COMPANY	AO-050-PJG-310-000327-REV04	REV	04	NA
CONTRACT	AO-050-PJG-310-000327	Project	AL	1 of 5
Document N°	ITM-0006039	Page	1	Class

H

A



NOTES:

NOTE 1. ONSHORE LIFTING RIGGING TO BE SUPPLIED BY CON ACCORDING TO CONTRACT.

REFERENCE:

AO-050-GMP-310-000379 MPP MODULE - GA DRAWING
AO-050-GMP-310-000380 SCM SKID - GA DRAWING
AO-050-GMP-310-000454 PUMP UNIT - GA DRAWING
AO-050-GSG-310-000347 SLS - GA DRAWING
AO-050-GSG-310-000358 FOUNDATION - GA DRAWING

ABBREVIATIONS:

Rev	Date	Status	Revision Memo	Issued by	Checked by	Approved by
04	28Apr2015	As Bld				
05	16Aug2015	AFC	Accepted for Construction	ATR	HMA	HMA
06	16Aug2015	AFC	Accepted for Construction	ATR	TNO	TNO
07	28Oct2015	AFC	Accepted for Construction	HMA	TNO	HMA
08	08Aug2015	RF	Issued for Review	RSU	FA	FA




Rev: 04
Scale: N/A
Format: A1
Sheet: 3 of 5


Scope of Supply, CPY

Doc Type	System/Line	Doc No	Revision	Doc Name
DRW	04	AO-050-PJG-310-000237-REV04	04	DRW
COMPANY		AO-050-PJG-310-000237	04	COMPANY
CONTRACT/CONTRACT		ITM-0006889	04	CONTRACT/CONTRACT

CAPITAL SPARES, TOOLS & SKIDS




BF TEST HPU




Transport skid for MFCF-RT x 2



MFCV - RT and insert transport and workover skid




MFCV Running Tool x 2




Transport skid for SCM x 2




Test and Transport skid for SCM x 1




FL Deployment frame, ind MECH x 7



Dummy MPP Module x 1




Subsea Storage Basket x 1




Dummy Foundation x 1



CF TEST HPU



FLDT x 2




Dummy Pump Unit x 4



FMC Connector Lift Yoke x 4




MeOH FMC Term Head x 1




1.8 MPP Station assembly

MPP Station as installed on sea bed.




1.9 Overview GirRI



1.10 Reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/1/	Flow assurance specification	AO-050-GSG-310-000120	DOC-0007898
/2/	MPP Module - data sheet	AO-050-GMP-310-000188	DOC-0010202
/3/	Pump Unit - data sheet	AO-050-GMP-310-000186	DOC-0010201
/4/	Foundation - data sheet	AO-050-GMP-310-000191	DOC-0010204
/5/	Support And Leveling Structure - data sheet	AO-050-GMP-310-000189	DOC-0010203
/6/	MPP system Scope of supply drawing	AO-050-PJG-310-000237	ITM-0009639
/7/	Control system design specification	AO-050-SSS-900-074451	DOC-0008350
/8/	Control fluid system design specification	AO-050-GSG-310-000025	DOC-0007895
/9/	Process flow diagram	AO-050-RMP-900-071923 AO-050-RMP-900-071924	DOC-0008510 DOC-0008511
/10/	Barrier fluid design specification	AO-050-GMP-310-000007	DOC-0007881
/11/	Monthly Weight Report	AO-050-PJG-310-002487	DOC-0074119
/12/	PCM - MPP Station HV, LV & FO Block Diagram	AO-050-PJG-310-000455	DRW-0004178
/13/	PCM - MPP Station BF & CF Block Diagram	AO-050-PJG-310-000597	DRW-0004287


2 Foundation



2.1 Foundation reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/14/	Foundation Data sheet	AO-050-GMP-310-000191	DOC-0010204
/15/	Foundation Interface Drawing	AO-050-GSG-310-000359	ITM-0058373
/16/	Foundation General Arrangement Drawing	AO-050-GSG-310-000358	ITM-0058358

2.1 Foundation features



2.1 Foundation Interface drawing

NOTES:

1. COG REF. 11/


					
--	---	---	---	---	---

Revision Status	Published	Made by	Checked by	Approved by
D	Released	2014-11-11 10:00:33 SH	SAA	HAA

797 DOC-00381317 AO-030-001-301-001112
LIFTING ANCHORE -



DETAIL A - 4 POSN
SCALE 3:20



Revision Status	Published	Made by	Checked by	Approved by
D	2016-11-10 00:33 SH	SAA	SAA	NAA
Engineering Change Order	ECN-00205			




SECTION D-D
SCALE 3:20



	TOTAL ESP ANGOLA		OneSubsea A Cesa-Submarine Company
---	-------------------------	---	--


3 SLS



3.1 SLS reference list


Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/17/	SLS Data sheet	AO-050-GMP-310-000189	DOC-0010203
/18/	SLS Interface Drawing	AO-050-GSG-310-000348	ITM-0058372
/19/	SLS General Arrangement Drawing	AO-050-GSG-310-000347	ITM-0058357

3.1 SLS features




3.2 SLS interface drawing


INTERFACES	
NO.	TO DESCRIPTION
13	ROV GRABBER BAR
14	MPP MPP MODULE LANDING POINT
16	CCP FUNNEL RETAINMENT BOLT FREE
17	ROV PARKING PANELS FOR HV AND BF FLYING LEADS
18	CCP FUNNEL RETAINMENT BOLT FIXED
19	CCP FUNNEL FOR FOUNDATION GUIDE POST
20	MPP ALIGNMENT MARKING
21	MPP LANDING POINTS FOR MPP MODULE
21	MOD SOFT LANDING CYLINDERS




DETAIL D
SCALE 1:20




DETAIL E
SCALE 3:20




SECTION A-A
SCALE 1:5



DETAIL F
SCALE 1:20



SECTION C-C
SCALE 1:10



DETAIL C
SCALE 3:50


NO.	DATE	BY	CHKD.	APP'D.	REV.	DESCRIPTION
01	20/04/2015	AFG	AFG	AFG	1	Approved for construction
02	20/04/2015	AFG	AFG	AFG	2	Approved for construction
03	20/04/2015	AFG	AFG	AFG	3	Approved for construction
04	20/04/2015	AFG	AFG	AFG	4	Approved for construction
05	20/04/2015	AFG	AFG	AFG	5	Approved for construction
06	20/04/2015	AFG	AFG	AFG	6	Approved for construction
07	20/04/2015	AFG	AFG	AFG	7	Approved for construction
08	20/04/2015	AFG	AFG	AFG	8	Approved for construction
09	20/04/2015	AFG	AFG	AFG	9	Approved for construction
10	20/04/2015	AFG	AFG	AFG	10	Approved for construction
11	20/04/2015	AFG	AFG	AFG	11	Approved for construction
12	20/04/2015	AFG	AFG	AFG	12	Approved for construction
13	20/04/2015	AFG	AFG	AFG	13	Approved for construction
14	20/04/2015	AFG	AFG	AFG	14	Approved for construction
15	20/04/2015	AFG	AFG	AFG	15	Approved for construction
16	20/04/2015	AFG	AFG	AFG	16	Approved for construction
17	20/04/2015	AFG	AFG	AFG	17	Approved for construction
18	20/04/2015	AFG	AFG	AFG	18	Approved for construction
19	20/04/2015	AFG	AFG	AFG	19	Approved for construction
20	20/04/2015	AFG	AFG	AFG	20	Approved for construction
21	20/04/2015	AFG	AFG	AFG	21	Approved for construction

Project: GIRRI PROJECT
Drawing: AO-050-GMP-310-000324
Revision: 02
Scale: 1:20
Sheet: 2 of 3


Approved by: [Signature]
Checked by: [Signature]
Drawn by: [Signature]

OneSubsea
SUPPORT AND LEVELING STRUCTURE -
INTERFACE DRAWING
ITM-0058372
Scale 1:50
Sheet 2 of 3

1. ITEM 01 AND 08
MAX RETRACTED POSITION: 275
NOMINAL POSITION: 645
MAX EXTENDED POSITION: 1025



4 MPP Module




4.1 MPP Module reference list


Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/20/	MPP Module P70 and P80 – Interface Drawing	AO-050-GMP-310-000380	ITM-0058434
/21/	MPP System – P&ID – MPP Station P70	AO-050-GSG-310-000102	DRW-0001208
/22/	MPP System – P&ID – MPP Station P80	AO-050-GSG-310-000103	DRW-0001209
/23/	MPP Module – General Arrangement Drawing	AO-050-GMP-310-000379	ITM-0058433
/24/	MPP Module – Data Sheet	AO-050-GMP-310-000188	DOC-0010202

4.2 MPP Module scope of supply

4.2.1 MPP Module P70 w/retrievable items



4.2.2 MPP Module P80 w/retrievable items



4.3 MPP Module interface drawing

[illegible]

 TOTAL TOTAL ESP ANGOLA		 OneSubsea A Cameron & McDaniel Company
---	---	--

MPP Module p70 and p80

Date Type :	System Unit:	Description :	Electronic Filenames
GFA	D4	MPP	AO-080-GMP-S10-000080-REV03
COMPANY:	Document #:	REV:	Rev:
Document F	AO-080-GMP-S10-000080	03	1/40 DE
CONFIRACTG09Original	ITLJ0006034	Format :	Falls : % of A.
		A4	4

DOCUMENT #	 OneSubsea A Cameron & Schlumberger Company	This drawing is the property of OneSubsea. It is not to be traded, copied, or reproduced without written consent. nor to be misused in any way.		IN THE EVENT OF A DISCREPANCY BETWEEN THE DRAWING AND THE SPECIFICATION, THE SPECIFICATION SHALL PREVAIL.
Title		MPP MODULE P70 AND P80		Weight

INTERFACE DRAWING		-
ID	Scale	
ITM-0058434		1:40
Format	A1	Sheet 2 of 6

Revision D	Status Released	Published 2014-12-19 10:40:35	Made by VES	Checked by SAA	Approved by Adm
---------------	--------------------	----------------------------------	----------------	-------------------	--------------------




INTERFACES		1		2		TOTAL E&P AMT	
NO.	TO	DESCRIPTION	NO.	TO	DESCRIPTION	NO.	TO
50	ROV	DISTIC INLET PROCESS HUB	50	ROV	DISTIC INLET PROCESS HUB	50	ROV
51		DISTIC OUTLET PROCESS HUB	51		DISTIC OUTLET PROCESS HUB	51	
70		BUMPER FOR 2ND DOCKHOUSE	70		BUMPER FOR 2ND DOCKHOUSE	70	
45		RIGHT BRANCH FROM MANIFOLD	45		RIGHT BRANCH FROM MANIFOLD	45	
		CONNECTED TO AFT PU			CONNECTED TO AFT PU		
46		GUIDE FUNNEL FOR SLS GUIDE POST	46		GUIDE FUNNEL FOR SLS GUIDE POST	46	
47		LEFT BRANCH FROM MANIFOLD	47		LEFT BRANCH FROM MANIFOLD	47	
		CONNECTED TO FORE PU			CONNECTED TO FORE PU		
80		ROV CONNECTOR PARKING RECEPTACLE R0	80		ROV CONNECTOR PARKING RECEPTACLE R0	80	
		CONTROL FLUID SUPPLY			CONTROL FLUID SUPPLY		
		RECEPTACLE FOR MALE HYDRAULIC CONNECTOR			RECEPTACLE FOR MALE HYDRAULIC CONNECTOR		
		TYPE: WATHER, R2			TYPE: WATHER, R2		
		RUNNING TORQUE: LOW			RUNNING TORQUE: LOW		
		DAMAGE TORQUE: 60Nm			DAMAGE TORQUE: 60Nm		
		DRIVE CHAINS TURNED TO CONNECT			DRIVE CHAINS TURNED TO CONNECT		
81		Signal parking	81		Signal parking	81	
82		TRONIC, FISH TAIL HANDLE INTERFACE	82		TRONIC, FISH TAIL HANDLE INTERFACE	82	
83		PULL TO DEHATE: 472-767N	83		PULL TO DEHATE: 472-767N	83	
		MAX RADIAL MISALIGNMENT: $\pm 20^{\circ}$			MAX RADIAL MISALIGNMENT: $\pm 20^{\circ}$		
84		MARK ROTATIONAL MISALIGNMENT: $\pm 5^{\circ}$	84		MARK ROTATIONAL MISALIGNMENT: $\pm 5^{\circ}$	84	




05	15-Nov-2014	AMS	Job-Title	V05	SWA	AMS	05	15-Nov-2014	AMS	Job-Title	V05	SWA	AMS
06	16-Nov-2014	AVC	Account for materials	V05	SWA	AMS	06	16-Nov-2014	AVC	Account for materials	V05	SWA	AMS
07	22-Nov-2014	IPR	Material to approved	V05	SWA	AMS	07	22-Nov-2014	IPR	Material to approved	V05	SWA	AMS
08	20-Dec-2014	IPR	Material to revision	ATTN	SWA	AMS	08	20-Dec-2014	IPR	Material to revision	ATTN	SWA	AMS
Rev	Date	Entered	Population Memo	Issued by Customer or Approved									
 													
THESE DOCUMENTS ARE THE PROPERTY OF ONE SUBSEA. THEY ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF ONE SUBSEA.													
MPP Module P70 and P80													
Interface Drawing													
Doc No:	Specification:	Design:	Revised Process:										
01	22-Nov-2014	Job-Title	REV: 1										
02	22-Nov-2014	Job-Title	REV: 2										
03	22-Nov-2014	Job-Title	REV: 3										
04	22-Nov-2014	Job-Title	REV: 4										
05	22-Nov-2014	Job-Title	REV: 5										
06	22-Nov-2014	Job-Title	REV: 6										
07	22-Nov-2014	Job-Title	REV: 7										
08	22-Nov-2014	Job-Title	REV: 8										
09	22-Nov-2014	Job-Title	REV: 9										
10	22-Nov-2014	Job-Title	REV: 10										
11	22-Nov-2014	Job-Title	REV: 11										
12	22-Nov-2014	Job-Title	REV: 12										
13	22-Nov-2014	Job-Title	REV: 13										
14	22-Nov-2014	Job-Title	REV: 14										
15	22-Nov-2014	Job-Title	REV: 15										
16	22-Nov-2014	Job-Title	REV: 16										
17	22-Nov-2014	Job-Title	REV: 17										
18	22-Nov-2014	Job-Title	REV: 18										
19	22-Nov-2014	Job-Title	REV: 19										
20	22-Nov-2014	Job-Title	REV: 20										
21	22-Nov-2014	Job-Title	REV: 21										
22	22-Nov-2014	Job-Title	REV: 22										
23	22-Nov-2014	Job-Title	REV: 23										
24	22-Nov-2014	Job-Title	REV: 24										
25	22-Nov-2014	Job-Title	REV: 25										
26	22-Nov-2014	Job-Title	REV: 26										
27	22-Nov-2014	Job-Title	REV: 27										
28	22-Nov-2014	Job-Title	REV: 28										
29	22-Nov-2014	Job-Title	REV: 29										
30	22-Nov-2014	Job-Title	REV: 30										
31	22-Nov-2014	Job-Title	REV: 31										
32	22-Nov-2014	Job-Title	REV: 32										
33	22-Nov-2014	Job-Title	REV: 33										
34	22-Nov-2014	Job-Title	REV: 34										
35	22-Nov-2014	Job-Title	REV: 35										
36	22-Nov-2014	Job-Title	REV: 36										
37	22-Nov-2014	Job-Title	REV: 37										
38	22-Nov-2014	Job-Title	REV: 38										
39	22-Nov-2014	Job-Title	REV: 39										
40	22-Nov-2014	Job-Title	REV: 40										
41	22-Nov-2014	Job-Title	REV: 41										
42	22-Nov-2014	Job-Title	REV: 42										
43	22-Nov-2014	Job-Title	REV: 43										
44	22-Nov-2014	Job-Title	REV: 44										
45	22-Nov-2014	Job-Title	REV: 45										
46	22-Nov-2014	Job-Title	REV: 46										
47	22-Nov-2014	Job-Title	REV: 47										
48	22-Nov-2014	Job-Title	REV: 48										
49	22-Nov-2014	Job-Title	REV: 49										
50	22-Nov-2014	Job-Title	REV: 50										
51	22-Nov-2014	Job-Title	REV: 51										
52	22-Nov-2014	Job-Title	REV: 52										
53	22-Nov-2014	Job-Title	REV: 53										
54	22-Nov-2014	Job-Title	REV: 54										
55	22-Nov-2014	Job-Title	REV: 55										
56	22-Nov-2014	Job-Title	REV: 56										
57	22-Nov-2014	Job-Title	REV: 57										
58	22-Nov-2014	Job-Title	REV: 58										
59	22-Nov-2014	Job-Title	REV: 59										
60	22-Nov-2014	Job-Title	REV: 60										
61	22-Nov-2014	Job-Title	REV: 61										
62	22-Nov-2014	Job-Title	REV: 62										
63	22-Nov-2014	Job-Title	REV: 63										
64	22-Nov-2014	Job-Title	REV: 64										
65	22-Nov-2014	Job-Title	REV: 65										
66	22-Nov-2014	Job-Title	REV: 66										
67	22-Nov-2014	Job-Title	REV: 67										
68	22-Nov-2014	Job-Title	REV: 68										
69	22-Nov-2014	Job-Title	REV: 69										
70	22-Nov-2014	Job-Title	REV: 70										
71	22-Nov-2014	Job-Title	REV: 71										
72	22-Nov-2014	Job-Title	REV: 72										
73	22-Nov-2014	Job-Title	REV: 73										
74	22-Nov-2014	Job-Title	REV: 74										
75	22-Nov-2014	Job-Title	REV: 75										
76	22-Nov-2014	Job-Title	REV: 76										
77	22-Nov-2014	Job-Title	REV: 77										
78	22-Nov-2014	Job-Title	REV: 78										
79	22-Nov-2014	Job-Title	REV: 79										
80	22-Nov-2014	Job-Title	REV: 80										
81	22-Nov-2014	Job-Title	REV: 81										
82	22-Nov-2014	Job-Title	REV: 82										
83	22-Nov-2014	Job-Title	REV: 83										
84	22-Nov-2014	Job-Title	REV: 84										
85	22-Nov-2014	Job-Title	REV: 85										
86	22-Nov-2014	Job-Title	REV: 86										
87	22-Nov-2014	Job-Title	REV: 87										
88	22-Nov-2014	Job-Title	REV: 88										
89	22-Nov-2014	Job-Title	REV: 89										
90	22-Nov-2014	Job-Title	REV: 90										
91	22-Nov-2014	Job-Title	REV: 91										
92	22-Nov-2014	Job-Title	REV: 92										
93	22-Nov-2014	Job-Title	REV: 93										
94	22-Nov-2014	Job-Title	REV: 94										
95	22-Nov-2014	Job-Title	REV: 95										
96	22-Nov-2014	Job-Title	REV: 96										
97	22-Nov-2014	Job-Title	REV: 97										
98	22-Nov-2014	Job-Title	REV: 98										
99	22-Nov-2014	Job-Title	REV: 99										
100	22-Nov-2014	Job-Title	REV: 100										
101	22-Nov-2014	Job-Title	REV: 101										
102	22-Nov-2014	Job-Title	REV: 102										
103	22-Nov-2014	Job-Title	REV: 103										
104	22-Nov-2014	Job-Title	REV: 104										
105	22-Nov-2014	Job-Title	REV: 105										
106	22-Nov-2014	Job-Title	REV: 106										
107	22-Nov-2014	Job-Title	REV: 107										
108	22-Nov-2014	Job-Title	REV: 108										
109	22-Nov-2014	Job-Title	REV: 109										
110	22-Nov-2014	Job-Title	REV: 110										
111	22-Nov-2014	Job-Title	REV: 111										
112	22-Nov-2014	Job-Title	REV: 112										
113	22-Nov-2014	Job-Title	REV: 113										
114	22-Nov-2014	Job-Title	REV: 114										
115	22-Nov-2014	Job-Title	REV: 115										
116	22-Nov-2014	Job-Title	REV: 116										
117	22-Nov-2014	Job-Title	REV: 117										
118	22-Nov-2014	Job-Title	REV: 118										
119	22-Nov-2014	Job-Title	REV: 119										
120	22-Nov-2014	Job-Title	REV: 120										
121	22-Nov-2014	Job-Title	REV: 121										
122	22-Nov-2014	Job-Title	REV: 122										
123	22-Nov-2014	Job-Title	REV: 123										
124	22-Nov-2014	Job-Title	REV: 124										
125	22-Nov-2014	Job-Title	REV: 125										
126	22-Nov-2014	Job-Title	REV: 126										
127	22-Nov-2014	Job-Title	REV: 127										
128	22-Nov-2014	Job-Title	REV: 128										
129	22-Nov-2014	Job-Title	REV: 129										
130	22-Nov-2014	Job-Title	REV: 130										
131	22-Nov-2014	Job-Title	REV: 131										
132	22-Nov-2014	Job-Title	REV: 132										
133	22-Nov-2014	Job-Title	REV: 133										
134	22-Nov-2014	Job-Title	REV: 134										
135	22-Nov-2014	Job-Title	REV: 135										
136	22-Nov-2014	Job-Title	REV: 136										
137	22-Nov-2014	Job-Title	REV: 137										
138	22-Nov-2014	Job-Title	REV: 138										
139	22-Nov-2014	Job-Title	REV: 139										
140	22-Nov-2014	Job-Title	REV: 140										
141	22-Nov-2014	Job-Title	REV: 141										
142	22-Nov-2014	Job-Title	REV: 142										
143	22-Nov-2014	Job-Title	REV: 143										
144	22-Nov-2014	Job-Title	REV: 144										
145	22-Nov-2014	Job-Title	REV: 145										
146	22-Nov-2014	Job-Title	REV: 146										
147	22-Nov-2014	Job-Title	REV: 147										
148	22-Nov-2014	Job-Title	REV: 148										
149	22-Nov-2014	Job-Title	REV: 149										
150	22-Nov-2014	Job-Title	REV: 150										
151	22-Nov-2014	Job-Title	REV: 151										
152	22-Nov-2014	Job-Title	REV: 152										
153	22-Nov-2014	Job-Title	REV: 153										
154	22-Nov-2014	Job-Title	REV: 154										
155	22-Nov-2014	Job-Title	REV: 155										
156	22-Nov-2014	Job-Title	REV: 156										
157	22-Nov-2014	Job-Title	REV: 157										
158	22-Nov-2014	Job-Title	REV: 158										
159	22-Nov-2014	Job-Title	REV: 159										
160	22-Nov-2014	Job-Title	REV: 160										
161	22-Nov-2014	Job-Title	REV: 161										
162	22-Nov-2014	Job-Title	REV: 162										
163	22-Nov-2014	Job-Title	REV: 163										
164	22-Nov-2014	Job-Title	REV: 164										
165	22-Nov-2014	Job-Title	REV: 165										
166	22-Nov-2014	Job-Title	REV: 166										
167	22-Nov-2014	Job-Title	REV: 167										
168	22-Nov-2014	Job-Title	REV: 168										
169	22-Nov-2014	Job-Title	REV: 169										
170	22-Nov-2014	Job-Title	REV: 170										
171	22-Nov-2014	Job-Title	REV: 171										
172	22-Nov-2014	Job-Title	REV: 172										
173	22-Nov-2014	Job-Title	REV: 173										
174	22-Nov-2014	Job-Title	REV: 174										
175	22-Nov-2014	Job-Title	REV: 175										
176	22-Nov-2014	Job-Title	REV: 176										
177	22-Nov-2014	Job-Title	REV: 177										
178	22-Nov-2014	Job-Title	REV: 178										
179	22-Nov-2014	Job-Title	REV: 179										
180	22-Nov-2014	Job-Title	REV: 180										
181	22-Nov-2014	Job-Title	REV: 181										
182	22-Nov-2014	Job-Title	REV: 182										
183	22-Nov-2014	Job-Title	REV: 183										
184	22-Nov-2014	Job-Title	REV: 184										
185	22-Nov-2014	Job-Title	REV: 185										
186	22-Nov-2014	Job-Title	REV: 186										
187	22-Nov-2014	Job-Title	REV: 187										
188	22-Nov-2014	Job-Title	REV: 188										
189	22-Nov-2014	Job-Title	REV: 189										
190	22-Nov-2014	Job-Title	REV: 190										
191	22-Nov-2014	Job-Title	REV: 191										
192	22-Nov-2014	Job-Title	REV: 192										
193	22-Nov-2014	Job-Title	REV: 193										
194	22-Nov-2014	Job-Title	REV: 194										
195	22-Nov-2014	Job-Title	REV: 195										
196	22-Nov-2014	Job-Title	REV: 196										
197	22-Nov-2014	Job-Title	REV: 197										
198	22-Nov-2014	Job-Title	REV: 198										
199	22-Nov-2014	Job-Title	REV: 199										
200	22-Nov-2014	Job-Title	REV: 200										
201	22-Nov-2014	Job-Title	REV: 201										
202	22-Nov-2014	Job-Title	REV: 202										
203	22-Nov-2014	Job-Title	REV: 203										
204	22-Nov-2014	Job-Title	REV: 204										
205	22-Nov-2014	Job-Title	REV: 205										
206	22-Nov-2014	Job-Title	REV: 206										
207	22-Nov-2014	Job-Title	REV: 207										
208	22-Nov-2014	Job-Title	REV: 208										
209	22-Nov-2014	Job-Title	REV: 209										
210	22-Nov-2014	Job-Title	REV: 210										
211	22-Nov-2014	Job-Title	REV: 211										
212	22-Nov-2014	Job-Title	REV: 212										
213	22-Nov-2014	Job-Title</											


[illegible]

MP7 Module P70 and P80 Interface Drawing		Part Name: MP7 Module P70 and P80 Part Number: AQ-0000-000-00000-REV00	
Rev Issued By Checked Approved	Quantity Unit Material Part Number Part Name Part Description	Rev Issued By Checked Approved	Quantity Unit Material Part Number Part Name Part Description
COMPANY: AQ-000-000-300-00000 PROJECT: AQ-000-000-300-00000 DRAWING: AQ-000-000-300-00000		Rev Issued By Checked Approved	
OneSubsea A COMPANY		Rev Issued By Checked Approved	
MP7 MODULE P70 AND P80 INTERFACE DRAWING		Rev Issued By Checked Approved	
Formal A1 Sheet 5 of 6		Rev Issued By Checked Approved	
Weight - Scale 33:100		Rev Issued By Checked Approved	
MP7 MODULE P70 AND P80 INTERFACE DRAWING		Rev Issued By Checked Approved	
Formal A1 Sheet 5 of 6		Rev Issued By Checked Approved	
Weight - Scale 33:100		Rev Issued By Checked Approved	
MP7 MODULE P70 AND P80 INTERFACE DRAWING		Rev Issued By Checked Approved	
Formal A1 Sheet 5 of 6		Rev Issued By Checked Approved	
Weight - Scale 33:100		Rev Issued By Checked Approved	



5 Process flow





5.1 Valve data

5.1.1 V2-1, V2-2

ATV 8" Hydr. Op. Slab Gate Valve, FSO, With ROV Override - operating information	
Nominal Input Torque	1900 Nm
Max allowable	2700 Nm
Damage	3000 Nm
No. of turns to open/close	92.3
Interface	ISO 13628-8, Class 4
Hydraulic fluid	Oceanic HW-443
Max Hydraulic supply pressure	345 Bar (5000 Psi)

5.1.2 V51-1, V51-2, V52-1, V52-2

ATV 8" ROV Op. Slab Gate Valve - operating information	
Nominal Input Torque	1900 Nm
Max allowable	2700 Nm
Damage	3000 Nm
No. of turns to open/close	33.9
Interface	ISO 13628-8, Class 4

5.1.3 V3-1A, V3-1B, V3-2A, V3-2B

8" Hydr. Op. Ball Valve, FSO, With ROV Override - operating information	
Nominal Input Torque	1900 Nm
Max allowable	2700 Nm
Damage	3000 Nm
No. of turns to open/close	14.1
Interface	ISO 13628-8, Class 4
Hydraulic fluid	Oceanic HW-443
Max Hydraulic supply pressure	345 Bar (5000 Psi)

5.1.4 V5-1, V5-2

ATV 6" Hydr. Op. Slab Gate Valve, FSO, With ROV Override - operating information	
Nominal Input Torque	1900 Nm
Max allowable	2700 Nm
Damage	3000 Nm
No. of turns to open/close	68.1
Interface	ISO 13628-8, Class 4
Hydraulic fluid	Oceanic HW-443
Max Hydraulic supply pressure	345 Bar (5000 Psi)

5.1.5 V70-1, V70-2

ATV 2" ROV Op. Slab Gate Valve - operating information	
Nominal Input Torque	1900 Nm
Max recommended	2700 Nm
Damage	3000 Nm
No. of turns to open/close	5
Interface	ISO 13628-8, Class 4

5.1.6 V71-1, V71-2, V72-1, V72-2

ATV 2" Hydr. Op. Gate Valve, FSC, With ROV Override - operating information	
Nominal Input Torque	1900 Nm
Max recommended	2700 Nm
Damage	3000 Nm
No. of turns to open/close	5
Interface	ISO 13628-8, Class 4
Hydraulic fluid	Oceanic HW-443
Max Hydraulic supply pressure	345 Bar (5000 Psi)

5.1.7 V82-1, V82-2

LB Bentley 1" Hydr. Op. Gate Valve, FSC, With ROV Override - operating information	
Running Torque	150 Nm
Max allowable	250 Nm
Damage	542 Nm
No. of turns to open/close	12 (+/- 0,5)
Interface	ISO 13628-8, Class 4
Hydraulic fluid	Oceanic HW-443
Max Hydraulic supply pressure	345 Bar (5000 Psi)

5.1.8 V80, V83-1, V83-2

LB Bentley 1" ROV Op. Gate Valve - operating information	
Running Torque	150 Nm
Max allowable	250 Nm
Damage	542 Nm
No. of turns to open/close	12 (+/- 0,5)
Interface	ISO 13628-8, Class 4

5.1.9 V20-1, V20-2, V30-1, V30-2

LB Bentley 3/4" ROV Op. Rotary Gate Valve - operating information	
Running Torque	176 Nm
Max allowable	407 Nm
Damage	610 Nm
No. of turns to open/close	1/4 (90 Deg)
Interface	ISO 13628-8, Class 4

5.1.10 V4-1, V4-2

Cameron 4" Compact Choke – operating information	
Max Running Torque	474.5 Nm
Damage	779 Nm
No. of Hyd. Pulses close/open	102
No. of turns to open/close	42
Interface	ISO 13628-8, Class 4
Hydraulic fluid	Oceanic HW-443
Max Hydraulic supply pressure	345 bar (5000 Psi)

5.1.11 CF1, CF2

Butech 2-way/90° Turn ROV Op. Ball Valve – operating information	
Max Running Torque	50 Nm
Max allowable	100 Nm
Damage	160 Nm
No. of turns to open/close	1/4 (90 Deg)
Interface	ISO 13628-8, paddle

5.2 MPP System – P&ID – MPP Station P70

GENERAL NOTES:

- A - All remotely actuated valves are with ROV override and ROV operator's Indicator.
- B - Flow Meter is to be provided for all process piping (By-pass header, MFL, BPL, Flow Meter, Flow Splitter, Pump Unit and connectors) and on length of small bore piping (MeOH, Demulsifier, Bleed off from line-in point to first isolation barrier (included).
- C - Thermal insulation to be provided for all process piping (By-pass header, MFL, BPL, Flow Meter, Flow Splitter, Pump Unit and connectors) and on length of small bore piping (MeOH, Demulsifier, Bleed off from line-in point to first isolation barrier (included).
- D - Schedule 160 applies for all piping (where ND is stated).
- E - Dummy Pump Units are interchangeable.

NOTES:


- 1 - Non-intrusive pig detector.
- 2 - Isolation Valve.
- 3 - Devalved.
- 4 - Minimum Flow Line overall length will be minimized for thermal performance. MFL will be connected to top of flow Meter.
- 5 - Flow Meter is to be provided for all process piping (By-pass header, MFL, BPL, Flow Meter, Flow Splitter, Pump Unit and connectors) and on length of small bore piping (MeOH, Demulsifier, Bleed off from line-in point to first isolation barrier (included).
- 6 - Hot stab connection.
- 7 - Bleed-off line tie-in on top of process piping (to be placed at highest point).
- 8 - NA.
- 9 - Isolation Valve and/or self-drained section from valve to connection point. 2: Valve located away from the connection point.
- 10 - Devalved.
- 11 - NA.
- 12 - NA.
- 13 - The upstream integrated double valve on the by-pass header is normally closed. The downstream integrated double valve is normally open.
- 14 - NA.
- 15 - NA.
- 16 - NA.
- 17 - NA.
- 18 - Maximum design temperature is only applicable for MPP Internals.
- 19 - MOC logisp.
- 20 - NA.
- 21 - NA.
- 22 - Uninsulated dummy Pump Unit.
- 23 - Dual gate valve.
- 24 - NA.
- 25 - NA.
- 26 - NA.

REFERENCES:

AO-050-SSS-310-000289 : MPP System - Subsea P&ID Legend Sheet

DESIGN PARAMETERS:

Design Pressure MPP Station : 345 bara
Design Temperature MPP Station : -18°C / 80°F



PUMP	
ITEM NUMBER	MPP70L OR MPP70R
SERVICE	PRODUCTION
TYPE	HELICOAXIAL PUMP
DESIGN	345
PRESSURE (bara)	94/151
MAX WORKING SUCTION DISCH.	-18/83
DESIGN MINMAX. NOTE 18.	50
OPERATING MIN	83
OPERATING MAX - BALANCE PISTON	77
OPERATING MAX - MPP DISCHARGE	130
MAX DIFFERENTIAL PRESSURE (bar)	2500
SHAFT POWER kW	

Revision	Date	Status	Revision Memo	Issued by	Checked by	Approved by
07	11-Mar-2014	AMB	AS BUILT	AMB	GSA	NA
08	13-Mar-2014	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
09	04-Jun-2014	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
10	19-Jun-2014	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
11	19-Jun-2014	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
12	19-Jun-2014	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
13	25-Jun-2014	IPR	ISSUED FOR ACCEPTANCE	AMB	GSA	NA
14	25-Jun-2014	IPR	ISSUED FOR REVIEW	AMB	GSA	NA

TOTAL E&P ANGOLA

OneSubsea

AO-050-GMP-310-000324

Doc Type : PD	System Unit : 04	Design : PRO	Design : MPP STATION 70
COMPANY : AO-050-GMP-310-000324	REV : 07	Scale : NONE	Phase : DE
CONTRACTOR : DRW-001208H	Format : A1	Page : 2 of 2	Class : 1
Revision Status	Issued by	Checked by	Approved by
Released	GSA	GSA	GSA
Engineering Change	0001-NA		

5.3 MPP System – P&ID – MPP Station P80

GENERAL NOTES:

- A - All remotely actuated valves are with ROV override and ROV operator's indicator.
- B - Thermal insulation to be provided for all process piping (by-pass header, MFL, BPL, Flow Mixer, Flow Splitter, Pump/Unit and connectors) and on length of small bore piping (MeOH, Demulsifier, Bleed off from line-in point to first isolation barrier (included).
- C - Thermal insulation to be provided for all process piping (by-pass header, MFL, BPL, Flow Mixer, Flow Splitter, Pump/Unit and connectors) and on length of small bore piping (MeOH, Demulsifier, Bleed off from line-in point to first isolation barrier (included).
- D - Schedule 160 applies for all piping (where ND is stated).
- E - Pump Units are Interchangeable.

NOTES:

- 1 - Non-intrusive pig detector.
- 2 - Demulsifier Span.
- 3 - Minimum Flow Line overall length will be minimized for thermal performance. MFL will be connected to top of flow mixer.
- 4 - MPP Station independently retrievable components: Choke insert and isolator, Chemical Valve and Pump Unit including MFL, discharge check valve and BPL.
- 5 - Isolated and/or self-drained section from valve to connection point. 2. Valve located at connection point.
- 6 - Deleted.
- 7 - NA.
- 8 - NA.
- 9 - Isolated and/or self-drained section from valve to connection point. 2. Valve located at connection point.
- 10 - Deleted.
- 11 - NA.
- 12 - NA.
- 13 - The upstream integrated double valve on the by-pass header is normally closed. The upstream integrated double valve is normally open.
- 14 - NA.
- 15 - NA.
- 16 - NA.
- 17 - NA.
- 18 - Minimum design temperature is only applicable for MPP Internals.
- 19 - MOC logic.
- 20 - NA.
- 21 - Methanol Isolation Valve (MIV) shall only open if methanol supply pressure is above 345 bars.
- 22 - Dual gase valve.
- 23 - Dual gase valve.
- 24 - NA.
- 25 - Dual gase valve.
- 26 - Dual gase valve.
- 27 - NA.
- 28 - Dual gase valve.

REFERENCES:

AO-050-GMP-310-000289 - MPP System - Subsea P&ID Legend Sheet

DESIGN PARAMETERS:

Design Pressure MPP Station : 345 bars
Design Temperature MPP Station : -10°C / 60°F

Revision	Date	Status	Revision Memo	Issued by	Checked by	Approved by
07	14-Jun-2014	AMB	AS BUILT	AMB	GSA	NA
08	14-Jun-2014	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
09	04-Nov-2013	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
10	04-Nov-2013	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
11	04-Nov-2013	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
12	14-Jun-2014	APC	ACCEPTED FOR CONSTRUCTION	AMB	GSA	NA
13	28-Nov-2011	IPR	ISSUED FOR ACCEPTANCE	AMB	GSA	NA
14	28-Nov-2011	IPR	ISSUED FOR ACCEPTANCE	AMB	GSA	NA



TOTAL E&P ANGOLA


This document is the property of COMPANY and shall not be released to third parties or reproduced without permission of the COMPANY.
This document shall be used for the purpose of design and construction only. It shall not be used for any other purpose.
This document shall be used for the purpose of design and construction only. It shall not be used for any other purpose.

Doc Type : PD	System/Unit : 04	Design : PRO	Subsea P&ID Legend Sheet
COMPANY : AO-050-GMP-310-000103	REV : 07	Scale : NONE	Phase : DE
CONTRACTOR : DRW-00120MH	Format : A1	Page : 2 of 2	Class : 1


MPP SYSTEM - P&ID - MPP STATION 80

PUMP

ITEM NUMBER	MPP80L OR MPP80R
SERVICE	PRODUCTION
TYPE	HELICOAXIAL PUMP
DESIGN	345
PRESSURE (bars)	94/151
MAX WORKING SUCTION DISCH.	-18/63
DESIGN MINMAX. NOTE 18.	50
OPERATING MIN	83
OPERATING MAX - BALANCE PISTON	77
MAX DIFFERENTIAL PRESSURE (bar)	130
SHAFT POWER KW	2500




6 Pump Unit



6.1 Pump Unit reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/25/	Pump Unit GA	AO-050-GMP-310-000454	ITM-0071499
/26/	Pump Unit Interface drawing	AO-050-GMP-310-000015	ITM-0077876

6.2 Pump Unit interface drawing



REFERENCES:

- 1/ RUNNING TOOL PUMP UNIT
AO-050-GMP-310-000621
- 2/ SURSEA SIGNAL JUMPER LAYOUT
DRW-0000852
- 3/ PUMP UNIT - GENERAL ARRANGEMENT
AO-050-GSG-310-000045
- 4/ MPP BARRIER FLUID SYSTEM SCHEMATIC
AO-050-GMP-310-000454
- 5/ MPP SYSTEM - P&ID - MPP STATION 80
DRW-0000885
- 6/ RETRIEVAL AND INSTALLATION GUIDELINE
AO-050-GSG-310-000103
- 7/ DOC-0022421
- 8/ AO-050-GMP-310-000459

Note:

1. Weight pump unit:

- Weighted weight:
- PU #1 (SN:13458) : 51,855kg
- PU #2 (SN:13460) : 51,855kg
- PU #3 (SN:13461) : 51,850kg
- PU #4 (SN:13462) : 52,033kg
- PU #5 (SN:13463) : 52,283kg
- PU #6 (SN:13464) : 51,967kg

Coc: 7/

Coc with tool. Sheet 5. Given in air.

ABBREVIATIONS:

- PM MPP Module




NO	DESCRIPTION	QTY	UNIT	QTY	UNIT	QTY	UNIT	QTY	UNIT
1	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
2	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
3	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
4	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
5	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
6	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
7	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
8	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
9	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
10	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS

NO	DESCRIPTION	QTY	UNIT	QTY	UNIT	QTY	UNIT	QTY	UNIT
1	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
2	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
3	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
4	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
5	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
6	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
7	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
8	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
9	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
10	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS

NO	DESCRIPTION	QTY	UNIT	QTY	UNIT	QTY	UNIT	QTY	UNIT
1	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
2	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
3	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
4	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
5	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
6	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
7	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
8	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
9	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS
10	ACTUATOR	1	PCS	1	PCS	1	PCS	1	PCS





SCALE 3:100

Technical drawing of the ROV system showing a main assembly view and two detailed views (DETAIL D and DETAIL C). The main view shows the ROV with various components labeled with callouts 1 through 21. Callouts 1-14 point to specific ROV components, while 15-21 point to interface components. Two detailed views are provided: DETAIL D (SCALE 2:25) shows a close-up of the top of the ROV with callouts 1, 2, 3, 9, 11, and 13. DETAIL C (SCALE 3:20) shows a close-up of the side of the ROV with callouts 14, 15, 16, and 18. The drawing includes dimensions and labels for various parts like valves, gauges, and connectors.

[illegible]

For operating inlet Destec clamp, use
grabber bar located on MPP Module


INTERFACES:	NO.	TO	
	24	PM	See sheet
	26	PM	Guides
	27	PM	Soft land
	28	PM	Interface and fem

[illegible]



INTERFACES:

21	ROV	IT	"RS2" Interface to installation tool base. Filled with grease. Receptacle for male hydraulic connector type Walther.
22	ROV	IT	Running torque: 40Nm Maximal torque: 160Nm Damage torque: 240Nm Turn CW (11.5 turns) to Connect "BP" Workover barrier oil return. Receptacle for male hydraulic connector type Walther.
23	ROV	IT	Running torque: 40Nm Maximal torque: 160Nm Damage torque: 240Nm Turn CW (11.5 turns) to Connect V7-JV7-2 ISO 13628-8 Class 4 torque interface. Hydraulic operated gate valve (FSO)
24	ROV	IT	Value BTO torque: 550Nm ROV nominal input torque: 1900Nm ROV maximum input torque: 2700Nm Damage torque: 3000Nm NO of Turns: 68.1 At 10 strokes, apply 0.25 turns in reverse rotation
25	PM		EAB 2 stage Soft Landing System for subsea installation tools and modules Bottom flange standard SL 190/270-300 Inlet/outlet pipe
26	PM		Guidepost and landing pad for PU
27	PM		Landing pad for PU

BOTTOM VIEW



Top view




PUMP UNIT - INTERFACE DRAWING

Doc Type	System Name	Engineer	Electronic Parameters	Doc No	Doc Rev
PM	AO-050-GMP-310-000324	AFG	AO-050-GMP-310-000324	001	01
Company	AO-050-GMP-310-000324	AFG	AO-050-GMP-310-000324	001	01
Doc No	AO-050-GMP-310-000324	AFG	AO-050-GMP-310-000324	001	01
Doc Rev	001	01	001	001	01
Rev	001	01	001	001	01
Drawn by	AFG	AFG	AFG	AFG	AFG
Checked by	AFG	AFG	AFG	AFG	AFG
Approved by	AFG	AFG	AFG	AFG	AFG
Drawn by	AFG	AFG	AFG	AFG	AFG
Checked by	AFG	AFG	AFG	AFG	AFG
Approved by	AFG	AFG	AFG	AFG	AFG
Drawn by	AFG	AFG	AFG	AFG	AFG
Checked by	AFG	AFG	AFG	AFG	AFG
Approved by	AFG	AFG	AFG	AFG	AFG

Logos for Total, OneSubsea, and Girri.

DETAIL G
SCALE 3:20


7 MPP




7.1 MPP reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/27/	Pump functional specification	AO-050-GMP-310-000086	DOC-0003905
/28/	Pump Performance Test Procedure	AO-050-GMP-310-000442	DOC-0022266
/29/	MPP GA	AO-050-GMP-310-000961	ITM-0070730
/30/	Pump selection	AO-050-GMP-310-000017	DOC-0003858
/31/	Basis of operation and control – Pump system	AO-050-GMP-310-000028	DOC-0007904


7.2 MPP overview



7.3 MPP details



7.4 MPP cross section



7.5 MPP GA drawing


7.6 MPP technical description

MPP parameters	Description
Number of pumps	6
Operation	According to operating scenarios in A0-050-GMP-310-000086
Pump Type:	Multiphase pump w/ balance piston
Pump Inlet/Outlet size:	8"
Drive	Electric, Variable Speed (VSD)
Location of Drive System	Power and Control module on deck
Motor Voltage	6.6 kV
Rated Motor Shaft Power:	2900 kW
Rated Motor frequency:	71.5 Hz
Rated motor torque	6507 Nm
Rated Speed:	4252 rpm
Speed Range:	1500 – 4620 rpm
Number of stages:	10
Impeller diameter:	320 mm
Max differential Pressure:	110 bar
Flow capacity (operating cond.)	552 Am3/h (P70 Left year 4)
Maximum GVF (operating cond.)	53 % (P80 Right year 4)
Design pressure	346 bar (on both process and barrier fluid)
Design temperature process	93 degC
Design temperature barrier fluid	70 degC


7.7 MPP working area

The figure below shows the operating envelope for P80 Right for year 4. Operating envelopes for other operating conditions are included in Pump Selection, ref. /30/.

A description of the operating envelope is included in Basis of Operation and Control – Pump System, ref. /31/.



7.8 MPP motor



7.9 MPP general requirements


- Variable speed drive (VSD) for each MPP.
- Recycle loop per MPP.
- The MPP have dedicated upstream flowmixer and downstream flow splitter
- The MPP have a built-in check valve at the MPP outlet.
- Barrier fluid supply for the MPP motor.
- The MPP to be installed in a Pump Unit that is interchangeable and retrievable.

7.10 MPP design conditions

Design conditions	Value	Comment
Maximum Pressure Differential	110 bar	Max dP limited to thrust bearing and balance piston.
Pump Design Pressure Process	346 bara	
Pump casing design pressure (process fluid exposed parts)	346 bara	
Pump casing (mixer housing) design temperature (process fluid exposed parts)	93 °C	
Pump casing hydrostatic test pressure at workshop (process fluid exposed parts)	495 barg	According to ASME VIII div. 2
Motor casing design pressure (barrier fluid exposed parts)	346 bara	
Motor casing design temperature (barrier fluid exposed parts)	85 °C	
Motor casing hydrostatic test pressure at work shop (barrier fluid exposed parts)	495 barg	According to ASME VIII div. 2 AO-050-GMP-310-000028
Process Fluid Normal Operating Temperature Range	4 – 77 °C	Flowing Condition
Barrier fluid design temperature	3.8 - 70 °C	
Ambient Sea water temperature max/min	4.4 / 3.8 °C	
Sea water pressure at pump location	146.8 bar	Ambient pressure of 1450m
Max. Design pressure external	150 bar	
Max GVF	100%	
Motor Rated Shaft Power	2900 kW	@ 4252 rpm
Maximum continuous speed	4620 rpm	

8 MPFM







The MPFM is part of the Pump Unit.



8.1 MPFM reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/32/	MPFM - GA drawing	AO-050-GMP-310-000411	ITM-0071600

8.1 MPFM GA drawing



NOTES:

NOTE 1: CONDUCTIVITY PROBE SYSTEM FINAL DIMENSIONS

NOTE 2: PW Vx SS Type F NAME PLATE: ITM-0064659

NOTE 3: WARNING LABEL FOR RADIOACTIVITY: ITM-0031835

NOTE 4: CATHODIC PROTECTION: SURFACE AREA ESTIMATED 8 m² COATED AREA. COVERS AND INSULATION NOT INCLUDED. ALL METAL SURFACES ELECTRICALLY CONNECTED TO CATHODIC PROTECTION SYSTEM ARE PAINTED.

NOTE 5: CENTRE OF GRAVITY: SEE DRAWING (CGG)

NOTE 6: WELDING ON STRUCTURES CONNECTED TO THE PHASEWATCHER Vx MAY ONLY BE PERFORMED IF APPROPRIATE ACTIONS HAVE BEEN TAKEN TO ENSURE THAT NO FLOW OF FLUIDS WILL FLOW THROUGH ANY PART OF THE Vx METER. FURTHER, THE Vx METER PARTS MUST NEVER BE EXPOSED TO HEAT FROM THE WELDING OPERATIONS (REF. STORAGE CONDITIONS -20 TO +50DEGC FOR SUBSEA Vx METER). FEASIBILITY CLAIMS IF THESE CONDITIONS ARE VIOLATED.

NOTE 7: SURFACE PROTECTION, REF DATA SHEET


NOTE 8: ESTIMATED WEIGHT IN AIR: 2600kg. ESTIMATED WEIGHT IN WATER: 2250kg

#	INTERFACES:
1	INLET: API 68X 7 1/16 FLANGE SEAL: BX-156 SEE TABLE FOR ALLOWABLE NOZZLE LOADS
2	OUTLET: API 68X 7 1/16 FLANGE 10K SEAL: BX-156 SEE TABLE FOR ALLOWABLE NOZZLE LOADS
3	ELECTRICAL CONNECTOR "A" ED V-20-8004-AA-DC-H012P DIGITRON, SIZE 20, WITH 12 WAY CONNECTOR (RECEPTACLE)
4	ELECTRICAL CONNECTOR "B" ED V-20-8004-AA-DC-H012P DIGITRON, SIZE 20, WITH 12 WAY CONNECTOR (RECEPTACLE)
5	STRUCTURAL ATTACHMENT 6 OFF M16 SPACED AS SHOWN
6	LIFTING EYELET, 4 OFF 1/2" EA

Q1	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q2	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q3	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q4	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q5	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q6	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q7	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q8	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q9	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q10	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q11	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q12	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q13	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q14	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q15	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q16	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q17	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q18	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q19	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q20	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q21	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q22	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q23	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q24	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q25	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q26	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q27	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q28	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q29	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q30	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q31	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q32	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q33	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q34	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q35	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q36	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q37	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q38	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q39	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q40	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q41	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q42	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q43	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q44	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q45	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q46	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q47	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q48	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q49	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q50	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q51	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q52	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q53	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q54	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q55	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q56	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q57	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q58	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q59	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q60	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q61	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q62	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q63	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q64	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q65	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q66	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q67	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q68	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q69	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q70	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q71	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q72	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q73	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q74	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q75	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q76	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q77	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q78	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q79	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q80	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q81	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q82	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q83	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q84	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q85	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q86	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q87	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q88	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q89	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q90	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q91	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q92	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q93	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q94	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q95	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q96	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q97	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q98	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q99	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN
Q100	19100215	ASB	ASB BUILT	MAA	ASB	MAN	MAN

		A Camrose & Schmalz Company		weight		Scale	1:10	Approved by
				NOTE				
				Scale				
				Scale				
Title		9060 GIRRI MPTM - GA DRAW ING		PW Vx SS TYPE F4, 8BU		Created by		Approved by
ID		ITM-0071600		Sheet		1 of 2		
Revision Status		Revised		Made by		Checked by		
Engineering Change Order		2014-05-23 17:20:18		2014-05-23 17:20:18		2014-05-23 17:20:18		

9 SCM



The SCM will be utilized to monitor and control the subsea pump modules P70 and P80 for GirRI.

Each pump module will be equipped with 1 off SCM which will interface all control and monitoring functions on the MPP Module.

One common SCM design shall ensure interchangeability between SCMs for the GirRI development.

The subsea pump control system is based on a standard OneSubsea Subsea Control Module (SCM); an electro hydraulic subsea pump control system with fibre optic communication. It will be equipped with two electronic modules; SEMs for redundancy, and a dielectric oil filled, pressure compensated compartment for the instrumented hydraulic system utilizing DCVs, pressure- and flow sensors.

The SCM is designed to be installed and retrieved by the use of OneSubsea SCM Installation Tool.


9.1 SCM reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/33/	SCM User Manual	AO-050-GSG-310-000472	DOC-0022249
/34/	SCM GA & Interface drawing	AO-050-GSG-310-000405	ITM-0059363
/35/	SCM Data Sheet	AO-050-GSG-310-000153	DOC-0003680
/36/	SCM Hydraulic Schematic	AO-050-GSG-310-000090	DRW-0001198



9.2 SCM scope of supply

SCM x 3


- SCM P70
- SCM P80
- SCM Spare



SCM Test & Transport Skid (SCM T&TS) x 1



SCM Transport Skid (SCM TS) x 2



9.3 SCM interface drawing

NOTES:

WEIGHT SCM (WEIGHED):
IN AIR: 4750 KG

WEIGHT SCM (CALCULATED):
SUBMERGED: 4100 KG

NOTE 01: ROV BUCKET CLASS 4
SCM INSTALLATION TOOL AND TORQUE TOOL
INTERFACE:
MAXIMUM TORQUE: 800 Nm
BREAK OUT TORQUE: 2000 Nm
DAMAGE TORQUE: 2000 Nm
NO. OF TURNS FULL TRAVEL: 30 1/2
NO. OF TURNS INSTALLATION: 25 1/2
CCW TO MAKE UP
CW TO DISCONNECT / RELEASE

NOTE 02: LOCKING HANDLES
LIFT AND ROTATE 60° CW TO LOCK
LIFT AND ROTATE 60° CCW TO OPEN

NOTE 03: ROV SIGNAL/V POWER CONNECTOR
MATING FORCE MAX: 500N
DEMATE FORCE: 600N
MAX RADIAL MISALIGNMENT: ± 20
MAX ANGULAR MISALIGNMENT: $\pm 20^\circ$
MAX ROTATIONAL MISALIGNMENT: $\pm 15^\circ$

NOTE 04: ROV FO CONNECTORS
MATING FORCE MAX: 36.5 KG
DEMATE FORCE: 36.5 KG
MAX RADIAL MISALIGNMENT: ± 35
MAX ANGULAR MISALIGNMENT: $\pm 30^\circ$
MAX ROTATIONAL MISALIGNMENT: $\pm 30^\circ$

NOTE 05: GUIDE POST FOR SCM INSTALLATION TOOL
NOTE 06: ACCUMULATOR PRE-CHARGE PORT
NUTTING PRE-CHARGE PORT, T OFF ACCUMULATOR
ON EACH SIDE

NOTE 07: HYDRAULIC RETURN FLUID VENT PORT

NOTE 08: SUBSEA ELECTRONIC MODULE (SEM)

NOTE 09: INSTALLATION INDICATORS
INSTALLATION MODE: UPPER ORANGE NOT VISIBLE
OPERATION MODE: LOWER ORANGE NOT VISIBLE

NOTE 10: INTERFACE FOR EYE BOLTS: M36
FOR TOPSIDE HANDLING (EYE BOLTS NOT SHOWN).
EYE BOLTS TO BE DELIVERED WITH SCM.
EYE BOLTS TO BE REMOVED PRIOR TO INSTALLATION

NOTE 11: MARKING FOR SECONDARY RELEASE CUT

REFERENCE DOCUMENTS:
SUBSEA CONTROL MODULE - USER MANUAL
AO-050-GSG-310-000472 (DOC-0022249)

SCM INSTALLATION TOOL GA & INTERFACE DRAWING
AD-050-GSS-310-000588 (DRW-0003536)

TAG NO:
P-270 SCM: 2-SCM-1706
P-80 SCM: 2-SCM-1806
SPARE SCM: 2-SCM-10055

Rev	Date	Status	Revision Memo	Drawn by	Checked by	Approved by
01	29/05/2014	AS BUILT				
02	15/06/2014	APC	Accepted for Construction			
03	23/07/2014	APC	Accepted for Construction			
04	15/08/2015	APC	Accepted for Construction			
05	15/08/2015	APC	Accepted for Construction			
06	15/08/2015	APC	Accepted for Construction			
07	15/08/2015	APC	Accepted for Construction			
08	15/08/2015	APC	Accepted for Construction			
09	15/08/2015	APC	Accepted for Construction			
10	15/08/2015	APC	Accepted for Construction			
11	15/08/2015	APC	Accepted for Construction			



OneSubsea
A Subsea Technology Company

Subsea Control Module
GA and Interface

Rev Type: 01
Rev Date: 29/05/2014
Rev Description: AS BUILT
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 02
Rev Date: 15/06/2014
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 03
Rev Date: 23/07/2014
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 04
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 05
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 06
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]







Rev Type: 07
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 08
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 09
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]

Rev Type: 10
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]


Rev Type: 11
Rev Date: 15/08/2015
Rev Description: APC
Rev By: [Signature]
Rev Checked: [Signature]
Rev Approved: [Signature]



ORANGE STRIPE
BLACK STRIPE
ORANGE STRIPE

2070 LOWER POSITION
2275 UPPER POSITION

10 MFCV (V4-1 / V4-2)





Minimum Flow Control Valve Body with Minimum Flow Valve Insert

10.1 MFCV reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/37/	General Arrangement Drawings with Parts List (Minimum Flow Valve)	AO-050- PJG-327-001415	DOC-0039547
/38/	Choke Data Sheet (Minimum Flow Valve)	AO-050-PJG-327-001408	DOC-0037949
/39/	Assembly Drawing, Assy Detail, Insert Assy	NA	DOC-0043207
/40/	MPP Module P70 and P80 – Interface Drawing	AO-050-GMP-310-000380	ITM-0058434

10.2 MFCV placement




10.1 MFCV technical description

CC40 SRC Compact Choke	MFCV data
Item Details	API 6A 20th Ed. / API 17D 2nd Ed / ISO 10423 / ISO 13628-4
Design Code	See SK-079548-20
Reference Drawing:	10,000 psi MWP
Pressure Rating	10,000 feet
Depth Rating	5 1/8" API 10k, Flanged inlet & outlet
End Connections	13.62" +/- 0.03" (346mm +/-0.8mm)
Distance Choke inlet to Outlet Centerline	13.62" +/- 0.03" (346mm +/-0.8mm)
Distance Choke Outlet to Inlet Centerline	"P-U" (-20oF to 250oF, -29 oC to 121 oC)
API Temperature Rating	"HH-NL"
API Material Class	2 ¼ Cr 1Mo LAS fully Ni alloy clad on process wetted surfaces
Body	25Cr Super Duplex Stainless Steel
Bonnet Material	718 Ni Alloy / Tungsten Carbide
Trim Material	Plug and Cage Eq. % with Max. Cv = 106 (Flow tested = 134)
Trim (Forward Flow)	Dog-in-Window Self Locking Connector with Mechanical Anti
Connector Type	Vibration Lock/Unlock
Primary Bonnet Seal	718 Ni Alloy metal lip seal.
Primary / Secondary Stem Seals	VaripakTM – Spring energized PTFE / U-Packing
Quality level	Manufactured to PSL 3G
F.A.T. testing	In Accordance With API 17D, Section 7.21.4.2 + Gas Test
Qualification	API 6A 20th Ed (ISO 10423) - PR2, API 17D (ISO 13628-4) Hyperbaric test to 10,000 feet water depth.


CC40 SRC Compact Choke	Actuator data
Type	Subsea Stepping Linear Choke Actuator SSLCA
Actuator Cleanliness	SAE AS4059 6B-F
Hydraulic Supply Pressure	5,000 psi
Control Fluid	Oceanic HW 443
Hydraulic Connections	2 off 3/8" x 0.065" (9.5mm x 1.7mm) Weld Tails
Hydraulic Swept Volume	0.64in3 (10.5cm3) per pulse
Temperature Rating	35 oF to 150 oF (2 oC to 66 oC)
Location Indicator	Graduated from 0 to 10. (0 closed, 10 open)
Electrical Feedback	LVDT, 4 – 20 mA Output, 10.5-28 VDC Input
Electrical Connector	4-way ODI Electrical Connector (Body half supplied by others)
No. of Hyd. Pulses to close	102 nominal. Operating times based on 3 Sec pulse time = 5.1 minutes
ROV Interface	API 17H / ISO 13628-8 Rotary interface Class 4
Operating Torque for Override	250 Ft. lbs max
Qualification	API 6A 20th Ed (ISO 10423) - PR2, API 17D (ISO 13628-4) Hyperbaric test to 10,000 feet water depth. & 1,000,000 pulse endurance test.

10.2 MFCV GA drawing

TOTAL E&P ANGOLA - GIRRI PROJECT - AO-050-PJG-327-001415 REV 03 - ASB - 20-NOV-2014




PARTIAL SECTION "A-A"
NOT TRUE VIEW




PARTIAL SECTION "D-D"
TYP. 2 PLCS.

CHOKE ASSY. WEIGHT: 880Kgs (N AIR).
BODY ASSY. WEIGHT: 540Kgs (N AIR)
INSERT ASSY. WEIGHT: 340Kgs (N AIR), 291Kgs (N WATER).
APPROX. CENTRE OF GRAVITY INDICATED BY


NOTE:
IF IT IS ANTICIPATED THAT MARINE GROWTH COULD OCCUR TO THE INTERFACES OF THE CHOKE
(I.E. PUSH/PULL RODS, HYD OVERRIDE, LIFT BUCKET),
CAMERON RECOMMEND THAT A MARINE GROWTH PROTECTION CAP IS PUT IN PLACE.



INSERT PARTIAL VIEW "B-B"
(WITH BODY REMOVED)



VIEW "C"




ELECTRICAL SCHEMATIC

TOTAL E&P ANGOLA - GIRRI PROJECT - AO-050-PJG-327-001415 REV 03 - ASB - 20-NOV-2014

ITEM No.	DESCRIPTION	REFERENCE DRAWING No.(s)	INTERVENTION DATA
1	PUSH-PULL RODS	---	ALL INFO PERTAINING TO FUNCTIONING OF THE PUSH PULL RODS CAN BE FOUND IN THE RUNNING TOOL OPERATION MANUAL.
2	OVERRIDE TORQUE RECEPTACLE	API 17H (ISO 13628-8) DOCKING ROTARY CLASS 4	OPERATING TORQUE = 200 Ft.Lbs. (272Nm). MAXIMUM TORQUE = 250 Ft.Lbs. (339Nm). DAMAGE TORQUE = 300 Ft.Lbs. (407Nm). No. OF TURNS OF OVERRIDE SHAFT FROM OPEN TO CLOSE = 8.5 APPROX.
3	LIFTING MANDREL	---	MAXIMUM LIFT FORCE OF 10,000 Lbs (44,482N) MAY BE APPLIED.
4	NATIONAL HYDRAULIC COUPLERS (4A) HYDRAULICALLY ACTUATED TO CLOSE. (4B) HYDRAULICALLY ACTUATED TO OPEN.	---	CONNECT TO CONTROL SYSTEM VIA 3/8" x .065" BUTT WELD TAIL ON MALE COUPLER WHICH IS SITUATED ON THE CHOKE BODY. DISTANCE FROM BODY WALL TO CENTRELINE OF WELD TAIL IS 5.9". (NO BACK PRESSURE RETURN LINE) EXHAUST TO SEA 316L STAINLESS STEEL WELD TAIL
5	OCEAN DESIGN 4 WAY ELECTRICAL STAB CONNECTOR, BULKHEAD	ODI P/N: 1015710 REF. DWG: X-249463-02	ODI CONNECTOR, STAB TYPE (ON RETRIEVABLE CHOKE INSERT) 4 WAY PIN CONTACTS (MALE) PIN 1 +VE, PIN 2 -VE, PINS 3 & 4 NOT TO BE TERMINATED (USED FOR IN HOUSE CALIBRATION). TYPICAL MATING CONNECTOR ODI P/N 1017461 (FINISHED WIRE OD AND COMPENSATION FLUIDS TO BE CONFIRMED WITH ODI). (TO BE SUPPLIED BY OTHERS AS PART OF THE JUMPER FROM SCM TO CHOKE BODY.) SCALE GRADUATED 0 TO 10, 0 = FULLY CLOSED, 10 = FULLY OPEN. SOME OVER TRAVEL IS PERMITTED.
6	VISUAL INDICATOR	---	
7	SSLCA ACTUATOR WITH LVDT	---	INPUT VOLTAGE 10.5-28 VDC, OUTPUT 4-20 mA, 4mA @ FULLY CLOSED, 20mA @ FULLY OPEN, SUBSEA STEPPING LINEAR CHOKE ACTUATOR FILLED WITH CHEVRON ULTRA ISO GR88 GEAR OIL.
8	CHOKE INSERT GUIDE PINS	---	DESIGNED TO ACCOMMODATE 3" MAXIMUM INSERT OFFSET IN ANY DIRECTION,
9	CC40 P & C TRIM		2.125" TRAVEL, APPROX. 102 PULSES FROM OPEN TO CLOSE.
10	HYDRAULIC SUPPLY DATA	N/A	MAXIMUM HYDRAULIC SUPPLY PRESSURE = 5,000 PSIG HYDRAULIC PULSE INTERVALS : 1 SECOND POWER, 2 SECONDS RETURN. RECOMMENDED INTERVALS TO BE VERIFIED DURING CONTROLS SYSTEM INTERFACE TESTING.
11	LOCKDOWN BAR	---	SECONDARY ANTI-VIBRATION LOCKDOWN BAR MIN. SETTING TORQUE = 60 FT LBS MAX. BREAKOUT TORQUE = 80 ft lbs MAX. SETTING TORQUE = 90 FT LBS MIN. BREAKOUT TORQUE = 20 ft lbs DAMAGE BREAKOUT TORQUE = 150 ft lbs NO OF TURNS TO LOCK AV BAR = 12+/-1.5 APPROX.
12	SECONDARY HYDRAULIC UNLOCK OVERRIDE	---	COUPLER ENGAGES WITH FEMALE HYDRAULIC COUPLER ON THE COMPACT CHOKE RUNNING TOOL. TO BE OPERATED USING THE RUNNING TOOL ONLY. EXPECTED OPERATING PRESSURE = 1,000 PSI MAXIMUM ALLOWABLE PRESSURE = 3,000 PSI
13	MARINE GROWTH COVER	---	COVER TO BE REMOVED BY ROV, PRIOR TO CHOKE INSERT INTERVENTION VIA CCRT.

TOTAL E&P ANGOLA - GIRRI PROJECT - AO-050-PJG-327-001415 REV 03 - ASB - 20-NOV-2014




11 DPU

11.1 DPU reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/41/	DPU – GA/Interface Drawing	AO-050-GMP-310-000534	ITM-0105865
/42/	DPU – Data Sheet	AO-050-GMP-310-001115	DOC-0029759

11.2 DPU scope of supply



DMPP in TS

11.3 DPU GA/interface drawing

INTERFACES:


NO.	TO	DESCRIPTION
1	ROV	Detec inlet process clamp ISO 15628-8: Hot Slab Interface Make up torque: 1381 Nm Break out torque: 1588 Nm Damage torque: 2700 Nm Damage torque to open: 80 Nm No. of turns: 26 CW to close
2	ROV	Detec inlet process clamp ISO 15628-8: Hot Slab Interface Make up torque: 1381 Nm Break out torque: 1588 Nm Damage torque: 2700 Nm Damage torque to open: 80 Nm No. of turns: 26 CW to close
14	IT	Pad eyes designed only for lifting with spreader beam or dedicated installation tool
3	ROV	Grabber Bars
4	ROV	Valves for Soft Landing Cylinder Pressure/temperature Transmitter Max operating torque: 100 Nm Damage torque: 160 Nm Turn 90 CCW to open
5	ROV	Receptacle for male hydraulic connector type hotstab, for Soft Landing Cylinder Running torque: 40 Nm Damage torque: 160 Nm Turn CW (11.5 turns) to Connect ISO 15628-8: Hot Slab Type B Push to mate Pull to de-mate
6	ROV	Remove Dummy Slab before installing/ retrial from PM
7	ROV	Pressure/Temperature Transmitter Receptacle for male hydraulic connector type hotstab, for Back Seal Test on hub Running torque: 40 Nm Damage torque: 160 Nm Turn CW (11.5 turns) to Connect ISO 15628-8: Hot Slab Type B Push to mate Pull to de-mate
8	ROV	Remove Dummy Slab before installing/ retrial from PM HV Test-Power Receptacle Turn 180° CW to engage locking Nominal: 900N (X-direction) Max: 2000N (X-direction) Turn 180° CCW to disengage locking Nominal: 30N (CCW) Max: 200Nm (CCW)

02	150.000314	ASIS	ASIS	02	150.000314	ASIS	ASIS	02	150.000314	ASIS	ASIS
03	150.000314	ASIS	ASIS	04	150.000314	ASIS	ASIS	05	150.000314	ASIS	ASIS
06	150.000314	ASIS	ASIS	07	150.000314	ASIS	ASIS	08	150.000314	ASIS	ASIS
09	150.000314	ASIS	ASIS	10	150.000314	ASIS	ASIS	11	150.000314	ASIS	ASIS
12	150.000314	ASIS	ASIS	13	150.000314	ASIS	ASIS	14	150.000314	ASIS	ASIS
15	150.000314	ASIS	ASIS	16	150.000314	ASIS	ASIS	17	150.000314	ASIS	ASIS
18	150.000314	ASIS	ASIS	19	150.000314	ASIS	ASIS	20	150.000314	ASIS	ASIS
21	150.000314	ASIS	ASIS	22	150.000314	ASIS	ASIS	23	150.000314	ASIS	ASIS
24	150.000314	ASIS	ASIS	25	150.000314	ASIS	ASIS	26	150.000314	ASIS	ASIS
27	150.000314	ASIS	ASIS	28	150.000314	ASIS	ASIS	29	150.000314	ASIS	ASIS
30	150.000314	ASIS	ASIS	31	150.000314	ASIS	ASIS	32	150.000314	ASIS	ASIS
33	150.000314	ASIS	ASIS	34	150.000314	ASIS	ASIS	35	150.000314	ASIS	ASIS
36	150.000314	ASIS	ASIS	37	150.000314	ASIS	ASIS	38	150.000314	ASIS	ASIS
39	150.000314	ASIS	ASIS	40	150.000314	ASIS	ASIS	41	150.000314	ASIS	ASIS
42	150.000314	ASIS	ASIS	43	150.000314	ASIS	ASIS	44	150.000314	ASIS	ASIS
45	150.000314	ASIS	ASIS	46	150.000314	ASIS	ASIS	47	150.000314	ASIS	ASIS
48	150.000314	ASIS	ASIS	49	150.000314	ASIS	ASIS	50	150.000314	ASIS	ASIS
51	150.000314	ASIS	ASIS	52	150.000314	ASIS	ASIS	53	150.000314	ASIS	ASIS
54	150.000314	ASIS	ASIS	55	150.000314	ASIS	ASIS	56	150.000314	ASIS	ASIS
57	150.000314	ASIS	ASIS	58	150.000314	ASIS	ASIS	59	150.000314	ASIS	ASIS
60	150.000314	ASIS	ASIS	61	150.000314	ASIS	ASIS	62	150.000314	ASIS	ASIS
63	150.000314	ASIS	ASIS	64	150.000314	ASIS	ASIS	65	150.000314	ASIS	ASIS
66	150.000314	ASIS	ASIS	67	150.000314	ASIS	ASIS	68	150.000314	ASIS	ASIS
69	150.000314	ASIS	ASIS	70	150.000314	ASIS	ASIS	71	150.000314	ASIS	ASIS
72	150.000314	ASIS	ASIS	73	150.000314	ASIS	ASIS	74	150.000314	ASIS	ASIS
75	150.000314	ASIS	ASIS	76	150.000314	ASIS	ASIS	77	150.000314	ASIS	ASIS
78	150.000314	ASIS	ASIS	79	150.000314	ASIS	ASIS	80	150.000314	ASIS	ASIS
81	150.000314	ASIS	ASIS	82	150.000314	ASIS	ASIS	83	150.000314	ASIS	ASIS
84	150.000314	ASIS	ASIS	85	150.000314	ASIS	ASIS	86	150.000314	ASIS	ASIS
87	150.000314	ASIS	ASIS	88	150.000314	ASIS	ASIS	89	150.000314	ASIS	ASIS
90	150.000314	ASIS	ASIS	91	150.000314	ASIS	ASIS	92	150.000314	ASIS	ASIS
93	150.000314	ASIS	ASIS	94	150.000314	ASIS	ASIS	95	150.000314	ASIS	ASIS
96	150.000314	ASIS	ASIS	97	150.000314	ASIS	ASIS	98	150.000314	ASIS	ASIS
99	150.000314	ASIS	ASIS	100	150.000314	ASIS	ASIS	101	150.000314	ASIS	ASIS
102	150.000314	ASIS	ASIS	103	150.000314	ASIS	ASIS	104	150.000314	ASIS	ASIS
105	150.000314	ASIS	ASIS	106	150.000314	ASIS	ASIS	107	150.000314	ASIS	ASIS
108	150.000314	ASIS	ASIS	109	150.000314	ASIS	ASIS	110	150.000314	ASIS	ASIS
111	150.000314	ASIS	ASIS	112	150.000314	ASIS	ASIS	113	150.000314	ASIS	ASIS
114	150.000314	ASIS	ASIS	115	150.000314	ASIS	ASIS	116	150.000314	ASIS	ASIS
117	150.000314	ASIS	ASIS	118	150.000314	ASIS	ASIS	119	150.000314	ASIS	ASIS
120	150.000314	ASIS	ASIS	121	150.000314	ASIS	ASIS	122	150.000314	ASIS	ASIS
123	150.000314	ASIS	ASIS	124	150.000314	ASIS	ASIS	125	150.000314	ASIS	ASIS
126	150.000314	ASIS	ASIS	127	150.000314	ASIS	ASIS	128	150.000314	ASIS	ASIS
129	150.000314	ASIS	ASIS	130	150.000314	ASIS	ASIS	131	150.000314	ASIS	ASIS
132	150.000314	ASIS	ASIS	133	150.000314	ASIS	ASIS	134	150.000314	ASIS	ASIS
135	150.000314	ASIS	ASIS	136	150.000314	ASIS	ASIS	137	150.000314	ASIS	ASIS
138	150.000314	ASIS	ASIS	139	150.000314	ASIS	ASIS	140	150.000314	ASIS	ASIS
141	150.000314	ASIS	ASIS	142	150.000314	ASIS	ASIS	143	150.000314	ASIS	ASIS
144	150.000314	ASIS	ASIS	145	150.000314	ASIS	ASIS	146	150.000314	ASIS	ASIS
147	150.000314	ASIS	ASIS	148	150.000314	ASIS	ASIS	149	150.000314	ASIS	ASIS
150	150.000314	ASIS	ASIS	151	150.000314	ASIS	ASIS	152	150.000314	ASIS	ASIS
153	150.000314	ASIS	ASIS	154	150.000314	ASIS	ASIS	155	150.000314	ASIS	ASIS
156	150.000314	ASIS	ASIS	157	150.000314	ASIS	ASIS	158	150.000314	ASIS	ASIS
159	150.000314	ASIS	ASIS	160	150.000314	ASIS	ASIS	161	150.000314	ASIS	ASIS
162	150.000314	ASIS	ASIS	163	150.000314	ASIS	ASIS	164	150.000314	ASIS	ASIS
165	150.000314	ASIS	ASIS	166	150.000314	ASIS	ASIS	167	150.000314	ASIS	ASIS
168	150.000314	ASIS	ASIS	169	150.000314	ASIS	ASIS	170	150.000314	ASIS	ASIS
171	150.000314	ASIS	ASIS	172	150.000314	ASIS	ASIS	173	150.000314	ASIS	ASIS
174	150.000314	ASIS	ASIS	175	150.000314	ASIS	ASIS	176	150.000314	ASIS	ASIS
177	150.000314	ASIS	ASIS	178	150.000314	ASIS	ASIS	179	150.000314	ASIS	ASIS
180	150.000314	ASIS	ASIS	181	150.000314	ASIS	ASIS	182	150.000314	ASIS	ASIS
183	150.000314	ASIS	ASIS	184	150.000314	ASIS	ASIS	185	150.000314	ASIS	ASIS
186	150.000314	ASIS	ASIS	187	150.000314	ASIS	ASIS	188	150.000314	ASIS	ASIS
189	150.000314	ASIS	ASIS	190	150.000314	ASIS	ASIS	191	150.000314	ASIS	ASIS
192	150.000314	ASIS	ASIS	193	150.000314	ASIS	ASIS	194	150.000314	ASIS	ASIS
195	150.000314	ASIS	ASIS	196	150.000314	ASIS	ASIS	197	150.000314	ASIS	ASIS
198	150.000314	ASIS	ASIS	199	150.000314	ASIS	ASIS	200	150.000314	ASIS	ASIS
201	150.000314	ASIS	ASIS	202	150.000314	ASIS	ASIS	203	150.000314	ASIS	ASIS
204	150.000314	ASIS	ASIS	205	150.000314	ASIS	ASIS	206	150.000314	ASIS	ASIS
207	150.000314	ASIS	ASIS	208	150.000314	ASIS	ASIS	209	150.000314	ASIS	ASIS
210	150.000314	ASIS	ASIS	211	150.000314	ASIS	ASIS	212	150.000314	ASIS	ASIS
213	150.000314	ASIS	ASIS	214	150.000314	ASIS	ASIS	215	150.000314	ASIS	ASIS
216	150.000314	ASIS	ASIS	217	150.000314	ASIS	ASIS	218	150.000314	ASIS	ASIS
219	150.000314	ASIS	ASIS	220	150.000314	ASIS	ASIS	221	150.000314	ASIS	ASIS
222	150.000314	ASIS	ASIS	223	150.000314	ASIS	ASIS	224	150.000314	ASIS	ASIS
225	150.000314	ASIS	ASIS	226	150.000314	ASIS	ASIS	227	150.000314	ASIS	ASIS
228	150.000314	ASIS	ASIS	229	150.000314	ASIS	ASIS	230	150.000314	ASIS	ASIS
231	150.000314	ASIS	ASIS	232	150.000314	ASIS	ASIS	233	150.000314	ASIS	ASIS
234	150.000314	ASIS	ASIS	235	150.000314	ASIS	ASIS	236	150.000314	ASIS	ASIS
237	150.000314	ASIS	ASIS	238	150.000314	ASIS	ASIS	239	150.000314	ASIS	ASIS
240	150.000314	ASIS	ASIS	241	150.000314	ASIS	ASIS	242	150.000314	ASIS	ASIS
243	150.000314	ASIS	ASIS	244	150.000314	ASIS	ASIS	245	150.000314	ASIS	ASIS
246	150.000314	ASIS	ASIS	247	150.000314	ASIS	ASIS	248	150.000314	ASIS	ASIS
249	150.000314	ASIS	ASIS	250	150.000314	ASIS	ASIS	251	150.000314	ASIS	ASIS
252	150.000314	ASIS	ASIS	253	150.000314	ASIS	ASIS	254	150.000314	ASIS	ASIS
255	150.000314	ASIS	ASIS	256	150.000314	ASIS	ASIS	257	150.000314	ASIS	ASIS
258	150.000314	ASIS	ASIS	259	150.000314	ASIS	ASIS	260	150.000314	ASIS	ASIS
261	150.000314	ASIS	ASIS	262	150.000314	ASIS	ASIS	263	150.000314	ASIS	ASIS
264	150.000314	ASIS	ASIS	265	150.000314	ASIS	ASIS	266	150.000314	ASIS	ASIS
267	150.000314	ASIS	ASIS	268	150.000314	ASIS	ASIS	269	150.000314	ASIS	ASIS
270	150.000314	ASIS	ASIS	271	150.000314	ASIS	ASIS	272	150.000314	ASIS	ASIS
273	150.000314	ASIS	ASIS	274	150.000314	ASIS	ASIS	275	150.000314	ASIS	ASIS
276	150.000314	ASIS	ASIS	277	150.000314	ASIS	ASIS	278	150.000314	ASIS	ASIS
279	150.000314	ASIS	ASIS	280	150.000314	ASIS	ASIS	281	150.000314	ASIS	ASIS
282	150.000314	ASIS	ASIS	283	150.000314	ASIS	ASIS	284	150.000314	ASIS	ASIS
285	150.000314	ASIS	ASIS	286	150.000314	ASIS	ASIS	287	150.000314	ASIS	ASIS
288	150.000314	ASIS	ASIS	289	150.000314	ASIS	ASIS	290	150.000314	ASIS	ASIS
291	150.000314	ASIS	ASIS	292	150.000314	ASIS	ASIS	293	150.000314	ASIS	ASIS
294	150.000314	ASIS	ASIS	295	150.000314	ASIS	ASIS	296	150.000314	ASIS	ASIS
297	150.000314	ASIS	ASIS	298	150.000314	ASIS	ASIS	299	150.000314	ASIS	ASIS
300	150.000314	ASIS	ASIS	301	150.000314	ASIS	ASIS	3			

INTERFACES:

NO.	TO	DESCRIPTION
9	PM	Guide post and Landing pad for DPU
10	PM	Landing pad for DPU
11	PM	EAB soil landing system for subsea installation of roots and modules. Bottom range: standard. SL 100270300
12	PM	Water damping: 200mm Water stroking: 70mm Hydraulic stroke: 300mm Interlock between male hub and female hub Nonparallel 2mm clearance between hub's


WITH INSTALLATION TOOL



SCALE 1:25

02	350.000314	ASB	As Built	REI	ASB	REI	REI
03	2000.000314	ACC	Accepted for Construction	CSS	REI	REI	REI
04	1700.000314	APP	Approved for Review	REI	REI	REI	REI
05	1700.000314	APP	Approved for Review	REI	REI	REI	REI
06	1700.000314	APP	Approved for Review	REI	REI	REI	REI
07	1700.000314	APP	Approved for Review	REI	REI	REI	REI
08	1700.000314	APP	Approved for Review	REI	REI	REI	REI
09	1700.000314	APP	Approved for Review	REI	REI	REI	REI
10	1700.000314	APP	Approved for Review	REI	REI	REI	REI
11	1700.000314	APP	Approved for Review	REI	REI	REI	REI
12	1700.000314	APP	Approved for Review	REI	REI	REI	REI
13	1700.000314	APP	Approved for Review	REI	REI	REI	REI
14	1700.000314	APP	Approved for Review	REI	REI	REI	REI
15	1700.000314	APP	Approved for Review	REI	REI	REI	REI
16	1700.000314	APP	Approved for Review	REI	REI	REI	REI
17	1700.000314	APP	Approved for Review	REI	REI	REI	REI
18	1700.000314	APP	Approved for Review	REI	REI	REI	REI
19	1700.000314	APP	Approved for Review	REI	REI	REI	REI
20	1700.000314	APP	Approved for Review	REI	REI	REI	REI
21	1700.000314	APP	Approved for Review	REI	REI	REI	REI
22	1700.000314	APP	Approved for Review	REI	REI	REI	REI
23	1700.000314	APP	Approved for Review	REI	REI	REI	REI
24	1700.000314	APP	Approved for Review	REI	REI	REI	REI
25	1700.000314	APP	Approved for Review	REI	REI	REI	REI
26	1700.000314	APP	Approved for Review	REI	REI	REI	REI
27	1700.000314	APP	Approved for Review	REI	REI	REI	REI
28	1700.000314	APP	Approved for Review	REI	REI	REI	REI
29	1700.000314	APP	Approved for Review	REI	REI	REI	REI
30	1700.000314	APP	Approved for Review	REI	REI	REI	REI
31	1700.000314	APP	Approved for Review	REI	REI	REI	REI
32	1700.000314	APP	Approved for Review	REI	REI	REI	REI
33	1700.000314	APP	Approved for Review	REI	REI	REI	REI
34	1700.000314	APP	Approved for Review	REI	REI	REI	REI
35	1700.000314	APP	Approved for Review	REI	REI	REI	REI
36	1700.000314	APP	Approved for Review	REI	REI	REI	REI
37	1700.000314	APP	Approved for Review	REI	REI	REI	REI
38	1700.000314	APP	Approved for Review	REI	REI	REI	REI
39	1700.000314	APP	Approved for Review	REI	REI	REI	REI
40	1700.000314	APP	Approved for Review	REI	REI	REI	REI
41	1700.000314	APP	Approved for Review	REI	REI	REI	REI
42	1700.000314	APP	Approved for Review	REI	REI	REI	REI
43	1700.000314	APP	Approved for Review	REI	REI	REI	REI
44	1700.000314	APP	Approved for Review	REI	REI	REI	REI
45	1700.000314	APP	Approved for Review	REI	REI	REI	REI
46	1700.000314	APP	Approved for Review	REI	REI	REI	REI
47	1700.000314	APP	Approved for Review	REI	REI	REI	REI
48	1700.000314	APP	Approved for Review	REI	REI	REI	REI
49	1700.000314	APP	Approved for Review	REI	REI	REI	REI
50	1700.000314	APP	Approved for Review	REI	REI	REI	REI
51	1700.000314	APP	Approved for Review	REI	REI	REI	REI
52	1700.000314	APP	Approved for Review	REI	REI	REI	REI
53	1700.000314	APP	Approved for Review	REI	REI	REI	REI
54	1700.000314	APP	Approved for Review	REI	REI	REI	REI
55	1700.000314	APP	Approved for Review	REI	REI	REI	REI
56	1700.000314	APP	Approved for Review	REI	REI	REI	REI
57	1700.000314	APP	Approved for Review	REI	REI	REI	REI
58	1700.000314	APP	Approved for Review	REI	REI	REI	REI
59	1700.000314	APP	Approved for Review	REI	REI	REI	REI
60	1700.000314	APP	Approved for Review	REI	REI	REI	REI
61	1700.000314	APP	Approved for Review	REI	REI	REI	REI
62	1700.000314	APP	Approved for Review	REI	REI	REI	REI
63	1700.000314	APP	Approved for Review	REI	REI	REI	REI
64	1700.000314	APP	Approved for Review	REI	REI	REI	REI
65	1700.000314	APP	Approved for Review	REI	REI	REI	REI
66	1700.000314	APP	Approved for Review	REI	REI	REI	REI
67	1700.000314	APP	Approved for Review	REI	REI	REI	REI
68	1700.000314	APP	Approved for Review	REI	REI	REI	REI
69	1700.000314	APP	Approved for Review	REI	REI	REI	REI
70	1700.000314	APP	Approved for Review	REI	REI	REI	REI
71	1700.000314	APP	Approved for Review	REI	REI	REI	REI
72	1700.000314	APP	Approved for Review	REI	REI	REI	REI
73	1700.000314	APP	Approved for Review	REI	REI	REI	REI
74	1700.000314	APP	Approved for Review	REI	REI	REI	REI
75	1700.000314	APP	Approved for Review	REI	REI	REI	REI
76	1700.000314	APP	Approved for Review	REI	REI	REI	REI
77	1700.000314	APP	Approved for Review	REI	REI	REI	REI
78	1700.000314	APP	Approved for Review	REI	REI	REI	REI
79	1700.000314	APP	Approved for Review	REI	REI	REI	REI
80	1700.000314	APP	Approved for Review	REI	REI	REI	REI
81	1700.000314	APP	Approved for Review	REI	REI	REI	REI
82	1700.000314	APP	Approved for Review	REI	REI	REI	REI
83	1700.000314	APP	Approved for Review	REI	REI	REI	REI
84	1700.000314	APP	Approved for Review	REI	REI	REI	REI
85	1700.000314	APP	Approved for Review	REI	REI	REI	REI
86	1700.000314	APP	Approved for Review	REI	REI	REI	REI
87	1700.000314	APP	Approved for Review	REI	REI	REI	REI
88	1700.000314	APP	Approved for Review	REI	REI	REI	REI
89	1700.000314	APP	Approved for Review	REI	REI	REI	REI
90	1700.000314	APP	Approved for Review	REI	REI	REI	REI
91	1700.000314	APP	Approved for Review	REI	REI	REI	REI
92	1700.000314	APP	Approved for Review	REI	REI	REI	REI
93	1700.000314	APP	Approved for Review	REI	REI	REI	REI
94	1700.000314	APP	Approved for Review	REI	REI	REI	REI
95	1700.000314	APP	Approved for Review	REI	REI	REI	REI
96	1700.000314	APP	Approved for Review	REI	REI	REI	REI
97	1700.000314	APP	Approved for Review	REI	REI	REI	REI
98	1700.000314	APP	Approved for Review	REI	REI	REI	REI
99	1700.000314	APP	Approved for Review	REI	REI	REI	REI
100	1700.000314	APP	Approved for Review	REI	REI	REI	REI

12 CCV (V81-1 / V81-2)





Chemical Control Valve (CCV) and Receptacle House

12.1 CCV reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/43/	CTV General Arrangement Drawing	AO-050-PJG-340-001625	DOC-0042761
/44/	MPP Module P70 and P80 – Interface Drawing	AO-050-GMP-310-000380	ITM-0058434
/45/	MPP System – Installation Guideline - Chemical Control Valve (CCV)	AO-050-GSG-310-002302	DOC-0064035
/46/	Receptacle House General Arrangement Drawing	AO-050-PJG-340-001561	DOC-0042072

12.2 CCV placement




12.3 CCV GA drawing

Name plate to contain:
O/R Serial no.:
O/R Part no.:
Client Part no.:
Client Line no.: / Rev


Total Doc. No.: NG50-2-300-SPS-SPAB-30-0218, point 9.1

Painted acc. to:

Low torque receptacle type A
(According to ISO 13628-8)



Interface for Class 4 Torque Tool
(According to ISO 13628-8)
Minimum installation torque: 100 Nm
Maximum installation torque: 200 Nm
Damage torque: 400 Nm



SCALE 1:10

ESTIMATED DRY WEIGHT: 65 KG
ESTIMATED SUBMERGED WEIGHT: 55 KG

TITLE - CHEMICAL THROTTLE VALVE

TITLE - CHEMICAL THROTTLE VALVE									
- - - - -									
Oceaneering Rotator AS, 4685 Made in Norway									
CONFIDENTIAL									
This drawing and its contents are the property of Oceaneering Rotator AS. No part of this drawing may be reproduced or transmitted in any form or by any means electronic or mechanical, including photocopying, recording, or by any information storage and retrieval system, without prior written permission from Oceaneering Rotator AS.									
DRAWING NO. GA000148									
SHEET 1 OF 1									
DATE: 14-10-2013									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									
SHEET 1 OF 1									
PROJECT NO. GA000148									
APPROVED BY: [Signature]									
CHECKED BY: [Signature]									
DRAWN BY: [Signature]									
SCALE: 2:5									
PROJECT NO. GA000148									
DRAWING NO. GA000148									

13 Tie in





STABCON flowline connector

13.1 Tie in reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/47/	Product Data Sheet, Termination Heads and Inboard Hubs, STABCON MK1	AO-050-GSG-325-000545	DOC-0047861
/48/	Product Data Sheet, Large Insulation Cap	AO-050-GSG-325-000797	DOC-0025577
/49/	Installation/commissioning Procedure, Subsea – intervention/Tie-in, large insulation cap	AO-050-GSG-325-001019	DOC-0028278
/50/	Installation/Commissioning Procedure, Subsea – Intervention/Tie-in, Well jumper flowline spool connection and disconnection procedure.	AO-050-GSG-325-001764	DOC-0061573
/51/	Term.head KC4.2-10, ID8, SPO, S1 Swivel GA	AO-050-GSG-325-000785	DOC-0026877
/52/	Cap, Insulation, Reinst., KC4.2-10, Large Type, Manifold Side, GA	AO-050-GSG-325-000780	DOC-0026679
/53/	Cap outboard, Insulation, KC4-10, GA	AO-050-GSG-325-000778	DOC-0026667

13.2 Tie in interface drawing





14 Jumpers and wiring


Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/54/	Subsea Jumper Layout Schematic P70	AO-050-GSG-310-001455	DRW-0002726
/55/	Subsea Jumper Layout Schematic P80	AO-050-GSG-310-001548	DRW-0002919
/56/	Ga Drawing Fiber Optical Test Connector Plug	AO-050-GSG-310-002171	DRW-0003780
/57/	Subsea Signal Jumper Layout	AO-050-GSG-310-000045	DRW-0000852
/58/	PBOF Jumper Assembly, Hydralight, 8FOSM, 45' Hose Exit, Fishtail Handle, 110m	AO-050-GSG-334-001382	DOC-0041480
/59/	SCM - SPCU FO Connection Diagram	AO-050-GSG-310-000604	DRW-0002108
/60/	SCM - SPCU LV Connection Diagram	AO-050-GSG-310-000474	DRW-0002105
/61/	General Arrangement Drawing For H#3	AO-050-GSG-331-002113	DOC-0054457
/62/	Subsea Signal Jumper Wiring Diagram	AO-050-GSG-310-000075	DRW-0001202
/63/	Hydraulic Single line Flying Leads – Interface drawing	AO-050-GSG-310-001759	DRW-0003114
/64/	GA Female Outboard Plate 7 Way (4POP) – HFL type 1	AO-050-GSG-357-000602	DOC-0034261
/65/	GA Female Outboard Plate 7 Way (4POP) – HFL type 2	AO-050-GSG-357-000603	DOC-0034262
/66/	GA Female Outboard Plate 7 Way (4POP) – HFL type 3	AO-050-GSG-357-001274	DOC-0034265
/67/	HV General Arrangement / Interface drawing	AO-050-GSG-310-001297	ITM-0084555

14.1 Signal jumper layout drawing





14.2 SCM-SPCU FO connection diagram



14.3 FO Flying Lead assembly drawing

NOTES:

1. SEE SAPL DRAWING 7741-101 FOR CONNECTOR INTERFACE DIMENSIONS.

2. SPECIFICATIONS:

CONNECTOR:
MATING STROKE LENGTH: 4.8 in (122 mm)
MAXIMUM ROTATIONAL MISALIGNMENT: 10°
MAXIMUM ANGULAR MISALIGNMENT: 0.25 in (6.4 mm)
MAXIMUM RADIAL MISALIGNMENT: 112.5 lbf (500N)
MAXIMUM FORCES: 50 lbf (222N)
MATE: DE-MATE:
HOSE:
MINIMUM BENDING RADIUS(OUTSIDE): 6.0 in. (152 mm)
MINIMUM BENDING RADIUS (INSIDE): 5.0 in. (125 mm)
PRE-CHARGE PRESSURE: 102 psi (7.0 bar)
CONNECTOR TO HOSE:
PULL FORCE @ 0°: 562 lbf (2500N)
PULL FORCE @ 90°: 281 lbf (1250N)

3. ELECTRO-CHEMICAL ETCH SEACON PART (DRAWING) NUMBER, REVISION LEVEL, SERIAL NUMBER AND CUSTOMER PART NUMBER (IF APPLICABLE) USING 10 PT HIGH CHARACTERS, WHERE SHOWN. NUMBERS SHALL BE LABELED AS FOLLOWS:
(PART NUMBER & REVISION LEVEL) PIN XXXX - XXX REV X
(SALES ORDER - LINE ITEM - SEQUENTIAL NUMBER) SIN XXXXXXX - XX - XXX

4. ATTACH WATER PROOF LABEL AT THESE LOCATIONS WITH THE FOLLOWING INFORMATION:

JUMPER PART (DRAWING) NUMBER AND REVISION
JUMPER SERIAL NUMBER
CUSTOMER PART NUMBER (IF APPLICABLE)

5. SECURE IN PLACE WITH CLEAR HEAT SHRINK SLEEVING.



6. PLACE TWO (2) PIECES OF LOOSE HEAT SHRINK TUBING ON EACH HOSE, 12 INCHES LONG, ON HOSE FOR CUSTOMER USE.

ESTIMATED WEIGHT (OIL FILLED):
IN AIR: 255.7 lbs (116.0 kg)
IN WATER: 170.5 lbs (77.3 kg)

OPTICAL TERMINATION

CONNECTOR	CONNECTOR
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8

MATERIAL: (TI GR 5)
PROCESS SPECS:
ASSEMBLY IAW SAPL-MPS-1080.
FACTORY ACCEPTANCE TESTING: REFER TO SALES ORDER.
OPERATION AND MAINTENANCE IAW SAPL-OMM-1013.




7	AR	5K441	M23535-212-C	SUMITUBE HEAT SHRINK TUBING, 2" CLEAR (NOT SHOWN)	POLYURETHANE
6	AR	2K588	DC200 / 100 CST	DOW CORNING COMPENSATION FLUID 100 CST (NOT SHOWN)	SILICONE
5	REF	99017	SC-2 1/2	PROTECTIVE CAP (NOT SHOWN)	LDPE
4	2	4EAN5	A140-111-55	13mm MK II PBOF HOSE ASSEMBLY, TI FITTINGS, 55m LONG	---
3	4	4EAN5	A066-121	FIBER MANAGEMENT SUB ASSEMBLY	---
2	1	4EAN5	A066-111	IN-LINE OPTICAL SPICE CHAMBER, NON-PRESSURE COMPENSATED	(TI GR 5)
1	2	4EAN5	7741-101	HYDRA-LIGHT, TOP ASSEMBLY, SM, FLYING LEAD, 8 - CHANNEL, FISHTAIL HANDLE	---

ITEM NO.	QTY.	CAGE	PART NUMBER	DESCRIPTION	MATERIAL	MATERIAL SPEC	NOTE
---	---	---	---	---	---	---	---
COPYRIGHT© SEACON ADVANCED PRODUCTS LLC							
SEACON ADVANCED PRODUCTS LLC 1321 NELIUS RD. - BELLVILLE, TEXAS - 77418							
PBOF JUMPER ASSEMBLY, HYDRA-LIGHT, 8FOSM, 45° HOSE EXIT, FISHTAIL HANDLE, 110m							
THIS DRAWING CONTAINS PROPRIETARY INFORMATION OF SEACON ADVANCED PRODUCTS LLC. IT IS STRICTLY CONFIDENTIAL AND NOT TO BE REPRODUCED OR DISCLOSED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF AN AUTHORIZED REPRESENTATIVE OF SEACON.							
FOR REVISION DETAILS EPDM DOCUMENT RECORD							
REV	DSN	DRN	CHK	APP	DATE		
Ap4	JAK	GDF					
SIZE				CAGE NO.	DWG NO.		
B				4EAN5	A218-101		
JOB NO.				16679			
WEIGHT:				6			
SCALE				1:24			
SHEET				1 OF 1			


14.4 SCM-SPCU LV connection diagram

Ref. Subsea Signal Jumper Layout /57/ H#3.



14.5 LV Flying Lead assembly drawing

TYPE/PART NUMBER	T31851-00
CONNECTOR A	BR0V-20-0003-BO-DC-H012P-VF
CONNECTOR B	BR0V-20-A003-BO-DC-H012S-VF
HOSE LENGTHS	110M
LABEL A	H#3 ITM-0052295
LABEL B	SCM
LABEL C	SDU
LABEL X	TRONIC PART No. & TRONIC SERIAL No.
WEIGHT IN AIR (Kg)	120.77Kg
WEIGHT IN WATER (Kg)	30.73Kg
MATERIAL	UNS S32550
REFERENCE TO ASSEMBLY DRAWING	DOC-0029429 & AO-050-GSG-331-0021H3
REFERENCE TO HANDLING PROCEDURES	DOC-0072937 & X-000595
REFERENCE TO WIRING SCHEMATIC	DOC-0040408 & AO-050-GSG-331-001496
OneSubsea PROJECT No. & ITM No.	9060 - ITM-0052295
INTERNAL PRESSURE	15 BAR
INTERNAL OIL TYPE	DOW CORNING 200 SILICONE OIL
HOSE BEND RADIUS	180mm
HOSE OUTSIDE DIAMETER BEFORE FILLING	32.0±0.6mm
REQUIRED MAKE/DE-MATE FORCE	<50 Kg/148-80 Kg/
GUIDE PIN LOCATION	0° POSITION
MAXIMUM RADIAL MISALIGNMENT	±20mm
MAXIMUM ANGULAR MISALIGNMENT	±2.0°
MAXIMUM ROTATIONAL MISALIGNMENT	±6°



END VIEW
OF RECEPTACLE
SCALE 2:1


END VIEW
OF PLUG
SCALE 2:1

[illegible]

GENERAL TOLERANCE UNLESS-SPECIFIED	ORIGINAL SURFACE	DIMENSIONS UNLESS OTHERWISE STATED	MATERIAL
LINEAR ±0.25 mm		mm	
ANGULAR ±0.5°			
SHARP CORNER REMOVAL	UNLESS SURFACE FINISH	FINISH	
BREAK CORNERS $\sqrt{R}$	UNLESS OTHERWISE SPECIFIED		
FILED SURF. 0.30 TYP	1/4" NPT-316 SS		

12-WAY ROV RECEPTACLE TO 12-WAY ROV PLUG INSTALLATION DRAWING

AT	1 OF 1
----	--------



14.6 Electrical jumper diagram





15 ROV intervention/ tooling

15.1 ROV intervention / tooling reference list


NO	To	Marking	Description
/68/	GA and Interface Drawing – SCM-IT	AO-050-GMP-310-000081	DRW-0003536
/69/	MFCV – Drawing for Running Tool	AO-050-GMP-327-001417	DOC-0039552
/70/	Running Tool Pump Unit GA/ Interface drawing	AO-050-GMP-310-000621	ITM-0081769
/71/	Pump Unit Installation Tool Simplified GA / Interface drawing	AO-050-GMP-310-002254	ITM-0128125
/72/	PU IT – Data Sheet	AO-050-GMP-310-000624	DOC-0022406
/73/	FLOT GA drawing	AO-050-GSG-340-001880	DOC-0048874
/74/	Lifting Anchor Assembly drawing	AO-050-GMP-367-001708	DOC-0042221
/75/	FLDF Type 1 GA drawing	AO-050-GMP-310-001516	ITM-0081459
/76/	FLDF Type 2 GA drawing	AO-050-GMP-310-001513	ITM-0091985
/77/	FLDF Type 3 GA drawing	AO-050-GMP-310-001515	ITM-0081481
/78/	Test HPU GA drawing	AO-050-GTO-370-001525	DOC-0027201

15.2 PU running tool

Running tool is used for installation of the Pump Unit.

15.3 PU installation tool

The PU-IT is designed for installation and retrieval of the PU. The tool contains a package with accumulators and compensators for barrier fluid that provide barrier fluid supply during installation, and make the PU able to remain pressurized without barrier fluid supply from umbilical for 21 days, given that process is equal to ambient pressure during subsea storage period. In addition there are accumulators for flushing and sampling of barrier fluid.



PU installation tool

The PU-IT is interfacing the 4 pad-eyes on top of the PU and mechanically locked onto the PU.


The BF jumper between the PU and PU-IT consist of a hose with Walther type 87-G08 female connectors in each end, one for BF supply and one for flushing and sampling.

Design pressure 345 bar. SWL 750 kN.

PU-IT shall not be used for installation / recovery of DPU.


15.4 Simplified PU installation tool

The Simplified Pump Unit installation tool is designed for installation and retrieval of the DPU. DPU is equipped with 6 off guiding feet towards DPU, these are also designed for landing feet when landed on ground. The DPU-IT is interfacing the 4 pad-eyes on top of the DPU and mechanically locked onto the DPU by use of 4 off locking handles.




15.1 SCM installation tool

SCM-IT is designed for installation and retrieval of the SCM. The SCM-IT is mechanically locked onto the SCM by use of ISO 13628-8, Class 4 Torque tool. The locking mechanism between the SCM and mounting base can be operated by use of the SCM-IT. There are two soft landing cylinders on the SCM-IT which is interfacing the Pump Module structure during SCM installation.




15.2 MFCV – Running tool

MFCV Insert replacement is performed by the MFCV - Running Tool (choke insert running tool). This is a purpose built deep water ROV operated Running Tool. Insert is fully vertically retrievable with no horizontal access necessary.



15.3 Flying Leads Deployment Frame





All flying leads between SDU/M801 and MPP Station are to be deployed from deployment frames. Flying leads are to be deployed from 3 different types of frames;


Deployment frame	Content	Lengths
Type 1 – (4 off) GA drawing, ref. /75/	3x HV Flying leads 1x Barrier fluid flying lead 1x Earth bonding flying lead	110m 110m 110m (on two of these frames)
Type 2 - (2 off) GA drawing, ref. /76/	2x Bundled Hydraulic flying leads 2x LV Flying leads 2x FO Flying leads	110m 110m 110m
Type 3 - (1 off) GA drawing, ref. /77/	1x MeOH	230m
Dimensions	7.5m long, 6.0m wide and 3.4m high	

This gives a total of 7 deployment frames for MPP station P70 and P80. All frames are based on the same dimensions and design, but with different configuration of parking panels and flying leads. Each Deployment frame is lifted with a two leg lifting sling, and has a mud mat interface against seabed. Included in the design is a compensation system for the CF lines in the HFL and accumulators for the BF flying lead. Coiling of flying leads is to be equally divided on each side of the frame, which allows ROV to lift out cable in two runs.

15.4 Tooling required

The necessary ROV tools for operations at the GirRI MPP system are listed below.

Description	Comment	Supplier
Torque tool Class 1-4	Standard ISO 13628-8 Class 1-4 torque tool.	Intervention contractor
Torque tool / Gear Class 6	For operation Support and leveling bolts at the SLS.	Intervention contractor
ROV hydraulic Oil Pack	For operating soft landing cylinders on Pump Unit and Dummy Pump Unit. Minimum pressure: 100barg Minimum volume: 50 liters Environmental friendly oil to be used.	Intervention contractor
FLOT: 	For installation / intervention of HFL's and CCV. Ref. /73/.	OneSubsea
Hot Stab 43mm 1 port: 	For operating bleed off line MPP Module. Design according to ISO 13628-8 type B hotstab.	OneSubsea

Hot Stab 43mm 2 ports 	For operating Soft landing cylinders on PU and DPU, and for performing back seal test on destec clamps placed on PU and DPU. Design according to ISO 13628-8 type B hotstab.	OneSubsea
Lifting Anchor 	For retrieval of SLS Guide post placed on Foundation.	OneSubsea
Test HPU 	HPU for testing.	OneSubsea

15.5 PU running tool interface drawing

Engineering Change Order: ECR-002969





15.1 PU installation tool interface drawing

REFERENCES:

AO-050-GMP-310-000454 / ITM-0071499
/1/ PUMP UNIT GENERAL ASSEMBLY
AO-050-GMP-310-000015 / ITM-0071676
/2/ PUMP UNIT INTERFACE DRAWING
AO-050-GMP-310-002238 / DOC-0060866
/3/ PU SIMPLIFIED INSTALLATION TOOL PRESERVATION, PACKING AND STORAGE PROCEDURE
AO-050-GMP-310-002239 / DOC-0060867
/4/ PU SIMPLIFIED INSTALLATION TOOL TRANSPORT AND HANDLING PROCEDURE
AO-050-GMP-310-001353 / DOC-0032854
/5/ PUMP UNIT INSTALLATION TOOL STRUCTURAL ANALYSIS REPORT
AO-050-GMP-310-002691 / DOC-0029237
/6/ PUMP UNIT - INSTALLATION AND RETRIEVAL GUIDELINE
ITM-0120543
/7/ NAME PLATE PU INSTALLATION TOOL
ITM-0122812
/8/ NAME PLATE INFORMATION IT
ITM-0122640
/9/ NAME PLATE INSPECTION IT

NOTES:

1. WEIGHT PUMP UNIT INSTALLATION TOOL SIMPLIFIED DRY WEIGHT: 3358.7 kg
PU IT SIMP. #1 (SERIAL NUMBER: 14145): 3358.7 kg
PU IT SIMP. #2 (SERIAL NUMBER: 14146): 3354.7 kg
AO-050-PJG-310-31300X, MONTHLY WEIGHT REPORT:
COG: STATED ON VIEWS
2. INTERFACES SEE SHEET 2
3. LASHING POINTS FOR TRANSPORT 10 PCS.
4. LIFTING SLINGS SHOWN FOR INFO
5. MARKING AND COLOURS : YELLOW RAL 9004
COLOUR STRUCTURE : YELLOW RAL 9004
COLOUR LIFTING POINT : ORANGE RAL 2004
COLOUR ROV INTERFACE : ORANGE RAL 2004
COLOUR MARKING : BLACK TEXT ON
MARKING: ROV : YELLOW BACKGROUND
W/MIN 50 MM HEIGHT



Rev	Date	Status	Revision Memo	Drawn by	Checked by	Approved by
01	20/02/2015	AWB	As Built			
02	19/02/2014	AWB	Accepted for Construction			
03	20/02/2014	AWB	Issued for installation			
04	20/02/2015	AWB	Issued for review			

PUMP UNIT INSTALLATION TOOL SIMPLIFIED GA / INTERFACE DRAWING

Drawn by: [Signature]
Checked by: [Signature]
Approved by: [Signature]


Project: AO-050-GMP-310-002234
Drawing: ITM-0128125
Scale: 1 of 2

OneSubsea
A Subsea Engineering Company

Division: [Division]
Project: [Project]
Drawing: [Drawing]
Scale: 1 of 2

Formal: A1
Sheet: 1 of 2
Scale: 1:20


16 Control system




16.1 Control system reference lists

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/79/	Control System Requirements	AO-050-GSG-310-000066	DOC-0007952
/80/	Control System Block Diagram	AO-050-GSG-310-000068	DRW-0000851
/81/	Control System Network Topology	AO-050-GSG-310-000072	DRW-0000849
/82/	Control System Operator Work Station (OWS) Network Topology	AO-050-PJG-310-001287	DRW-0002555
/83/	Subsea Control System Power Supply - Single Line Diagram	AO-050-GSG-310-000190	DRW-0001704
/84/	Subsea Control System Fiber Optic (FO) Communication Single Line Diagram	AO-050-GSG-310-000461	DRW-0002094
/85/	SCM - SPCU FO Connection Diagram	AO-050-GSG-310-000604	DRW-0002108
/86/	SCM - SPCU LV Connection Diagram	AO-050-GSG-310-000474	DRW-0002105
/87/	Cause and Effect (C&E) Diagrams	AO-050-PJG-310-000613	DOC-0023010
/88/	Control System Subsea CANBus Layout	AO-050-GSG-310-000071	DRW-0000850
/89/	Subsea Signal Jumper Layout	AO-050-GSG-310-000045	DRW-0000852
/90/	MPP Barrier Fluid Schematic	AO-050-GMP-310-000089	DRW-0000885
/91/	Control Fluid – System Schematic	AO-050-GSG-310-000092	DRW-0000884
/92/	Barrier Fluid – System Layout Schematic	AO-050-GMP-310-000093	DRW-0000883
/93/	Demulsifier and MeOH Distribution Schematic	AO-050-GSL-310-000088	DRW-0001197


16.2 Block diagram P70



16.3 Block diagram P80



16.4 Control fluid schematic




16.5 Control fluid data

Control fluid is supplied from the PCM Control Fluid HPU, through the Topside Umbilical Termination Unit and subsea through the MPP umbilical. Further, control fluid is transferred from the subsea Umbilical Termination Assembly to the SCM mounting base located on the MPP Module. This interface is via single hydraulic jumpers and tubing. The SCM distributes the control fluid to the actuated valves and chokes on the MPP module through control fluid tubing.

Description		MacDermid Oceanic HW443
Appearance		Clear Fluorescent Yellow Green Fluid
pH		9.7
Specific Gravity @ 15.6°C		1.07
Kinematic viscosity at:		
	÷20°C	25.0 cSt
	0°C	9.2 cSt
	40°C	2.5 cSt
Max & min operating temperature		-25°C - +145°C
Pour Point		-25°C
SAE AS 4059		6B-F or better
Designed for use:		Open and closed loop subsea production control systems

17 Barrier system

17.1 Barrier fluid schematics




17.2 Barrier fluid data

Description		Data
Oil type		Shell Morlina S2 BL5
Bulk modulus		1.7 GPa
Thermal expansion coefficient		0.0007 1/°C
Specific Gravity @ 15.6°C		0.870
Flash point		120°C
Kinematic viscosity at:		
	4°C	17 cSt
	40°C	5 cSt
SAE AS 4059		6B-F or better
Maximum water content		Water content requirement of 50 ppm

18 PCM


PCM details are described in PCM Equipment Manual, ref. /97/.




18.1 PCM reference list

Ref	Document title	COMPANY Doc. No	MPP CON Doc. No
/94/	PCM General Arrangement External Layout	AO-050-GTO-311-000180	DOC-0010194
/95/	PCM General Arrangement Internal Layout	AO-050-GTO-311-000177	DOC-0010191
/96/	PCM - Safety Plot Plan	AO-050-GTO-310-000006	DRW-0001166
/97/	PCM P70 And P80 Equipment Manual	AO-050-GTO-310-002275	DOC-0062447
/98/	PCM P70 And P80 Penetration Arrangement	AO-050-GTO-311-000301	DOC-0020853
/99/	PCM MCT Schedule	AO-050-PJG-310-001475	DOC-0040235
/100/	Topside Equipment Tag List	AO-050-GTO-310-000159	DOC-0019727

18.2 PCM internal




Plan view P70




Plan view P80

P70 PCM Equipment	
Item	Service Description
1	PCM P70
2	Inergen Bottlebank
3	Safety Equipment Cabinet
4	Stretcher
5	MCC 1
6	LV 1
7	SPCU 1
8	UCP 1
9	HVAC UCP 1
10	VSD P70R
11	VSD P70L
12	VSD P70R Input Transformer
13	VSD P70L Input Transformer
14	VSD P80L Output Transformer
15	Barrier Fluid Purifier
16	Barrier Fluid HPU
17	Control Fluid HPU
18	ACU A
19	ACU B



P80 PCM Equipment	
Item	Service Description
101	PCM P80
102	Inergen Bottlebank
103	Safety Equipment Cabinet
104	Stretcher
105	MCC 2
106	LV 2
107	SPCU 2
108	UCP 2
109	HVAC UCP 2
110	VSD P80R
111	VSD P80L
112	VSD P80R Input Transformer
113	VSD P80L Input Transformer
114	VSD P80R Output Transformer
115	Barrier Fluid Nitrogen Booster Pump
116	Barrier Fluid HPU
117	Control Fluid HPU
118	ACU C
119	ACU D



18.3 PCM internal assembly drawing



Section A-A
PLAN VIEW PCM P70



Section B-B
PLAN VIEW PCM P80

General Tolerances:
Tolerances shall be in accordance to
Total spec: GSE PSTR 301. Ch. 14.

NOTES:

Item	Service Description	Area	Equipment	Section	Seq.	Equipment Tag
1	PCM P70	41	JA	0	20	41-040-20
2	Inergen Bottle Bank	41	JA	0	701	41-JF-9701
3	Safety Equipment Cabinet	41	UB	9	702	41-UB-9702
4	MCC 1	41	PD	9	703	41-UB-9703
5	LV 1	41	PD	9	704	41-UB-9704
6	LV 2	41	PD	9	705	41-UB-9705
7	LV 3	41	PD	9	706	41-UB-9706
8	LV 4	41	PD	9	707	41-UB-9707
9	HVAC UCP 1	41	AM	9	708	41-UB-9708
10	VSD P70R	41	AM	9	709	41-UB-9709
11	VSD P70L	41	AM	9	710	41-UB-9710
12	VSD P70	41	AM	9	711	41-UB-9711
13	VSD P70L	41	AM	9	712	41-UB-9712
14	VSD P70	41	AM	9	713	41-UB-9713
15	VSD P70L	41	AM	9	714	41-UB-9714
16	Barrier Fluid HPU	41	UB	9	715	41-UB-9715
17	Control Fluid HPU	41	UB	9	716	41-UB-9716
18	Control Fluid HPU	41	UB	9	717	41-UB-9717
19	ACU B	41	UB	9	718	41-UB-9718
20	ACU A	41	UB	9	719	41-UB-9719

Item	Service Description	Area	Equipment	Section	Seq.	Equipment Tag
101	PCM P80	41	JA	0	30	41-040-30
102	Inergen Bottle Bank	41	JA	0	801	41-JF-9801
103	Safety Equipment Cabinet	41	UB	9	802	41-UB-9802
104	MCC 2	41	PD	9	803	41-UB-9803
105	LV 1	41	PD	9	804	41-UB-9804
106	LV 2	41	PD	9	805	41-UB-9805
107	LV 3	41	PD	9	806	41-UB-9806
108	LV 4	41	PD	9	807	41-UB-9807
109	HVAC UCP 2	41	AM	9	808	41-UB-9808
110	VSD P80R	41	AM	9	809	41-UB-9809
111	VSD P80L	41	AM	9	810	41-UB-9810
112	VSD P80	41	AM	9	811	41-UB-9811
113	VSD P80L	41	AM	9	812	41-UB-9812
114	VSD P80	41	AM	9	813	41-UB-9813
115	VSD P80L	41	AM	9	814	41-UB-9814
116	Barrier Fluid HPU	41	UB	9	815	41-UB-9815
117	Control Fluid HPU	41	UB	9	816	41-UB-9816
118	Control Fluid HPU	41	UB	9	817	41-UB-9817
119	ACU D	41	UB	9	818	41-UB-9818

REFERENCES



DOC. NO:	PCM-P70 AND P80 INTERNAL LAYOUT
AO-050-GTO-311-000178	SECTIONS
AO-05-GTO-311-000180	PCM-P70 AND P80 GENERAL ARRANGEMENT EXTERNAL

Revision	Date	Status	Revision Memo	Checked by	Approved by
01	15/04/2015	AM	AS BUILT	DK	AM
02	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
03	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
04	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
05	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
06	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
07	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
08	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
09	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
10	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
11	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
12	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
13	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
14	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
15	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
16	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
17	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
18	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
19	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM
20	15/04/2015	AM	ACCEPTED FOR CONSTRUCTION	DK	AM

TOTAL E&P ANGOLA		Revision Memo		Checked by		Approved by	
Doc Type: LAY		System/Unit: 83		Discipline: STR		Accuracy: As per contract	
Company: AO-050-GTO-311-000177		Rev: 05		Scale: 1:50		Phase: DE	
Contract/Original		Sample Ref		Formal: At		Class: 1	
Document No		Doc-001831		Formal: At		Class: 1	

NOTES:
1. All dimensions are in millimeters.
2. All dimensions are to centerline unless otherwise specified.
3. All dimensions are to be confirmed by the contractor.
4. All dimensions are to be confirmed by the contractor.
5. All dimensions are to be confirmed by the contractor.
6. All dimensions are to be confirmed by the contractor.
7. All dimensions are to be confirmed by the contractor.
8. All dimensions are to be confirmed by the contractor.
9. All dimensions are to be confirmed by the contractor.
10. All dimensions are to be confirmed by the contractor.
11. All dimensions are to be confirmed by the contractor.
12. All dimensions are to be confirmed by the contractor.
13. All dimensions are to be confirmed by the contractor.
14. All dimensions are to be confirmed by the contractor.
15. All dimensions are to be confirmed by the contractor.
16. All dimensions are to be confirmed by the contractor.
17. All dimensions are to be confirmed by the contractor.
18. All dimensions are to be confirmed by the contractor.
19. All dimensions are to be confirmed by the contractor.
20. All dimensions are to be confirmed by the contractor.

18.4 PCM external



18.5 PCM external assembly drawing

NOTES:

1. The base plates are part of the PCM structure
2. For interface loads see AO-050-GTO-311-000432
3. For material grades and category see doc. no:
AO-050-GTO-311-000276 PCM - P70 AND P80 MATERIAL SCHEDULE.
4. External Ducting not shown.
5. For stopper details, see Bumper Arrangement:
AO-050-GTO-311-000741

REFERENCES

DOC. NO:	PCW - P70 AND P80 INTERNAL LAYOUT PLAN VIEW
AO-050-GTO-311-000177	
AO-050-GTO-311-000178	PCW - P70 AND P80 INTERNAL LAYOUT SECTIONS
AO-050-GTO-311-000181	PCW STACK - P70 AND P80 FOOTPRINT WITH DETAILS
AO-050-GTO-311-000183	PCW - P70 AND P80 STRUCTURAL INTERFACE BETWEEN P70 AND TLM
AO-050-GTO-311-000276	PCW P70 AND P80 MATERIAL SCHEDULE REPORT
AO-050-GTO-311-000432	PCW P70 AND P80 STRUCTURAL CALCULATION REPORT IN-PLACE
AO-050-GTO-311-000741	PCW P70 AND P80 BUMPER ARRANGEMENT
AO-050-GTO-311-000938	PCW P70 AND P80 HEAT SHIELD LAYOUT AND INSTALLATION


[illegible]

NOTES	DATE	STATUS	REVISIONS	ISSUED BY	DATE	APPROVED BY
 TOTAL E&P ANGOLA			 FRANCO ENGINEERING A Solihull-based Company			


This document is the property of COMPANY and shall not be loaned to third parties or reproduced without permission of COMPANY.

PCM P70 AND P80 ADVANCEMENT EXTENDS


Doc Type : GE A		System/Unit: 83		Discipline : STR		Electronic Filename AO-050-GTO-311-000180_rev06.pdf	
COMPANY Document N°		AO-050-GTO-311-000180		REV: 06		Scale: 1:100	
Contractor/Original Document N°		DOC-0010194		Supplier Ref: 2017-03-10-000261_006		Phase: DE	
				Format: A1		Folio: 1 of 2	
						Class: 1	




North wall




Top view




Detail 6 (1 : 15)
Connection Detail 6 (Index CD6)




Section 6A-6A




Detail 4 (1 : 15)
Connection Detail 4 (Index CD4)




Section 4A-4A




Section 2A-2A




Detail 3 (1 : 15)
Connection Detail 3 (Index CD3)



Section 3A-3A



Section 1A-1A




Connect



ance to
Ch. 14.

General Tolerances:
Tolerances shall be in accordance to
Total spec: GS EP STR 301, Ch. 14.



SECTION 7A-7A (1.10)
(Typical Section of Junction Box Arrangement)



Detail 7 (1:20)
(Junction Box Arrangement same in P70 and P80)
(Corrugated plates hidden for clarity)

Detail 7

NOTES:

REFERENCES

DOC. NO:	PCM P70 AND P80 GENERAL ARRANGEMENT EXTERNAL SHEET 01
AO-050-GTO-311-000180	
DOC. NO:	PCM - P70 AND P80 INTERNAL LAYOUT PLAN VIEW
AO-050-GTO-311-000177	
DOC. NO:	PCM - P70 AND P80 INTERNAL LAYOUT SECTIONS
AO-050-GTO-311-000178	
DOC. NO:	PCM STACK - P70 AND P80 FOOTPRINT WITH DETAILS
AO-050-GTO-311-000181	
DOC. NO:	PCM - P70 AND P80 STRUCTURAL INTERFACE BETWEEN P70 AND TLM
AO-050-GTO-311-000183	
DOC. NO:	PCM P70 AND P80 MATERIAL SCHEDULE REPORT
AO-050-GTO-311-000276	
DOC. NO:	PCM P70 AND P80 STRUCTURAL CALCULATION REPORT IN PLACE
AO-050-GTO-311-000432	
DOC. NO:	PCM P70 AND P80 BUMPER ARRANGEMENT
AO-050-GTO-311-000741	
DOC. NO:	PCM P70 AND P80 HEAT SHIELD LAYOUT AND INSTALLATION
AO-050-GTO-311-000308	

Item	Item Description	Unit	Quantity	Unit Price	Amount	Remarks
06	14-04-20-24	ASB	ASB 18.7	DN	DN	AS
07	14-04-20-25	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
08	14-04-20-26	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
09	14-04-20-27	ANC	ACCEPTED FOR CONSTRUCTION	M	DN	AS
02	14-04-20-28	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
03	14-04-20-29	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
04	14-04-20-30	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
05	14-04-20-31	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
01	14-04-20-32	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
02	14-04-20-33	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
03	14-04-20-34	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
04	14-04-20-35	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
05	14-04-20-36	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
06	14-04-20-37	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
07	14-04-20-38	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
08	14-04-20-39	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
09	14-04-20-40	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
10	14-04-20-41	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
11	14-04-20-42	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
12	14-04-20-43	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
13	14-04-20-44	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
14	14-04-20-45	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
15	14-04-20-46	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
16	14-04-20-47	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
17	14-04-20-48	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
18	14-04-20-49	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
19	14-04-20-50	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
20	14-04-20-51	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
21	14-04-20-52	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
22	14-04-20-53	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
23	14-04-20-54	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
24	14-04-20-55	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
25	14-04-20-56	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
26	14-04-20-57	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
27	14-04-20-58	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
28	14-04-20-59	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
29	14-04-20-60	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
30	14-04-20-61	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
31	14-04-20-62	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
32	14-04-20-63	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
33	14-04-20-64	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
34	14-04-20-65	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
35	14-04-20-66	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
36	14-04-20-67	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
37	14-04-20-68	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
38	14-04-20-69	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
39	14-04-20-70	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
40	14-04-20-71	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
41	14-04-20-72	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
42	14-04-20-73	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
43	14-04-20-74	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
44	14-04-20-75	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
45	14-04-20-76	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
46	14-04-20-77	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
47	14-04-20-78	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
48	14-04-20-79	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
49	14-04-20-80	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
50	14-04-20-81	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
51	14-04-20-82	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
52	14-04-20-83	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
53	14-04-20-84	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
54	14-04-20-85	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
55	14-04-20-86	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
56	14-04-20-87	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
57	14-04-20-88	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
58	14-04-20-89	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
59	14-04-20-90	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
60	14-04-20-91	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
61	14-04-20-92	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
62	14-04-20-93	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
63	14-04-20-94	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
64	14-04-20-95	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
65	14-04-20-96	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
66	14-04-20-97	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
67	14-04-20-98	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
68	14-04-20-99	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
69	14-04-20-100	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
70	14-04-20-101	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
71	14-04-20-102	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
72	14-04-20-103	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
73	14-04-20-104	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
74	14-04-20-105	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
75	14-04-20-106	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
76	14-04-20-107	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
77	14-04-20-108	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
78	14-04-20-109	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
79	14-04-20-110	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
80	14-04-20-111	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
81	14-04-20-112	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
82	14-04-20-113	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
83	14-04-20-114	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
84	14-04-20-115	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
85	14-04-20-116	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
86	14-04-20-117	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
87	14-04-20-118	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
88	14-04-20-119	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
89	14-04-20-120	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
90	14-04-20-121	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
91	14-04-20-122	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
92	14-04-20-123	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
93	14-04-20-124	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
94	14-04-20-125	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
95	14-04-20-126	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
96	14-04-20-127	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
97	14-04-20-128	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
98	14-04-20-129	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
99	14-04-20-130	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
100	14-04-20-131	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
101	14-04-20-132	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
102	14-04-20-133	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
103	14-04-20-134	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
104	14-04-20-135	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
105	14-04-20-136	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
106	14-04-20-137	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
107	14-04-20-138	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
108	14-04-20-139	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
109	14-04-20-140	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
110	14-04-20-141	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
111	14-04-20-142	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
112	14-04-20-143	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
113	14-04-20-144	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
114	14-04-20-145	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
115	14-04-20-146	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
116	14-04-20-147	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
117	14-04-20-148	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
118	14-04-20-149	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
119	14-04-20-150	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
120	14-04-20-151	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
121	14-04-20-152	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
122	14-04-20-153	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
123	14-04-20-154	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
124	14-04-20-155	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
125	14-04-20-156	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
126	14-04-20-157	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
127	14-04-20-158	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
128	14-04-20-159	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
129	14-04-20-160	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
130	14-04-20-161	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
131	14-04-20-162	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
132	14-04-20-163	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
133	14-04-20-164	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
134	14-04-20-165	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
135	14-04-20-166	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
136	14-04-20-167	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
137	14-04-20-168	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
138	14-04-20-169	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
139	14-04-20-170	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
140	14-04-20-171	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
141	14-04-20-172	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
142	14-04-20-173	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
143	14-04-20-174	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
144	14-04-20-175	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
145	14-04-20-176	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
146	14-04-20-177	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
147	14-04-20-178	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
148	14-04-20-179	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
149	14-04-20-180	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
150	14-04-20-181	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
151	14-04-20-182	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
152	14-04-20-183	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
153	14-04-20-184	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
154	14-04-20-185	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
155	14-04-20-186	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
156	14-04-20-187	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
157	14-04-20-188	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
158	14-04-20-189	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
159	14-04-20-190	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
160	14-04-20-191	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
161	14-04-20-192	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
162	14-04-20-193	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
163	14-04-20-194	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
164	14-04-20-195	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
165	14-04-20-196	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
166	14-04-20-197	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
167	14-04-20-198	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
168	14-04-20-199	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
169	14-04-20-200	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
170	14-04-20-201	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
171	14-04-20-202	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
172	14-04-20-203	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
173	14-04-20-204	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
174	14-04-20-205	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
175	14-04-20-206	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
176	14-04-20-207	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
177	14-04-20-208	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
178	14-04-20-209	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
179	14-04-20-210	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
180	14-04-20-211	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
181	14-04-20-212	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
182	14-04-20-213	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
183	14-04-20-214	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
184	14-04-20-215	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
185	14-04-20-216	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
186	14-04-20-217	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
187	14-04-20-218	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
188	14-04-20-219	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
189	14-04-20-220	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
190	14-04-20-221	ANC	ACCEPTED FOR CONSTRUCTION	DN	DN	AS
191	14-04-20-222	ANC	ACCEPTED FOR CONSTRUCTION</			

[illegible]

This document is the property of COMPANY and shall not be disclosed to third parties or reproduced without permission of the COMPANY. This document has been generated by the Microsoft Document Workspace. When in printout, it will be converted to "the information only copy". The content of this document is the property of COMPANY and shall not be disclosed to third parties or reproduced without permission of the COMPANY.

PCM P70 AND P80GENERAL ARRANGEMENT EXTERNAL[illegible]

Log type : GEA	SystemUnit: 83	Discipline : S I R	AO 090-GTO:311-000180_rev06.pdf
COMPANY		AO 090-GTO 014 000400	...

Document No	AU-050-G 10-3 11-000 180		REV: 06	Scale: 1:100	Phase: DE
Contractor/Original	Supplier				

Document N°	DOC-0010194	Ref.	2107-03/44-XD-000.20.2_008	Format :	A1	Folio :	2 of 2	Class :	1
-------------	-------------	------	----------------------------	----------	----	---------	--------	---------	---

18.1 PCM equipment



Transformers



VSD Room Toward LV Room



LV Room (SPCU,MCC,LV/UPS,HVAC)



BF Oil Purifier



BF HPU – P70 and P80



CF HPU P70 and P80



Safety Systems – Detection



Safety Systems - Inergen and Foam

18.2 PCM transport and installation



Assembly in Norway



Transport to Angola



Stack up in Angola (TLM on top of PCM)



Offshore lifting to Girassol FPSO

PROJECT DOCUMENTS

COMMENTS TO COMMENTS

DATE: 25.03.2015

CONTRACT: 9060 GirRI

MULTIPHASE PUMP SYSTEM

CPY doc.no: AO-050-GMP-310-000324

GirRI MPP HANDBOOK

Revision: 01

CON doc.no: DOC-0067899-B

Ref.	Comment	Reply	Action
1.	SAL: Since this document can also be used in digital forma, please include bookmarks on pdf file	Bookmarks included.	Implemented
2.	SFR: There are 7 x FL deployment frames with ITM No. from 0108001 to 0108007. Please clarify.	ITM-number for each frame included	Implemented
3.	SMO is it really same number as for P70?	Typo, updated	Updated
4.	SFR: 4 + 0 = 6 ??? Please correct.	Comments to other documents / drawings should not be included here. Latest revision of drawing included in Handbook.	Implemented

Revision Status	Published	Made by	Checked by	Approved by
C Released	2015-04-27 17:00:27 SAA		HAA	IFA
Engineering Change Order: NA				